

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Three Rivers 16-36T-820				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT THREE RIVERS				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR ULTRA RESOURCES INC						7. OPERATOR PHONE 303 645-9810				
8. ADDRESS OF OPERATOR 304 Inverness Way South #245, Englewood, CO, 80112						9. OPERATOR E-MAIL dghani@ultrapetroleum.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-49319			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		699 FSL 1311 FEL		SESE	16	8.0 S	20.0 E	S		
Top of Uppermost Producing Zone		1300 FSL 1880 FEL		SWSE	16	8.0 S	20.0 E	S		
At Total Depth		1300 FSL 1880 FEL		SWSE	16	8.0 S	20.0 E	S		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 699			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 46			26. PROPOSED DEPTH MD: 6591 TVD: 6457				
27. ELEVATION - GROUND LEVEL 4684			28. BOND NUMBER 022046398			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 1033	24.0	J-55 LT&C	8.8	Premium Lite High Strength	80	2.97	11.5
							Class G	115	1.16	15.8
PROD	7.875	5.5	0 - 6591	17.0	J-55 LT&C	10.0	Halliburton Light , Type Unknown	225	3.54	11.0
							Premium Lite High Strength	450	1.349	14.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton					TITLE Permitting Agent			PHONE 435 719-2018		
SIGNATURE					DATE 02/06/2014			EMAIL starpoint@etv.net		
API NUMBER ASSIGNED 43047542890000					APPROVAL Permit Manager					

ULTRA RESOURCES, INC.

MASTER
8 - POINT DRILLING PROGRAM

Slim Hole Design
8 5/8" Surface & 5 1/2" Production Casing Design

DATED: 03-27-14

**Directional Wells located on Ultra leases in
Three Rivers Project:**

Three Rivers Fed 16-36T-820

SHL: Sec 16 (SESE) T8S R20E

Uintah, Utah

ONSHORE OIL & GAS ORDER NO. 1
Approval of Operations on Onshore
Federal and Indian Oil and Gas Leases

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (CFR 43, Part 3160) and the approved Application for Permit to Drill. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations.

RECEIVED: April 04, 2014

1. Formation Tops

The estimated tops of important geologic markers are as follows:

<u>Formation Top</u>	<u>Top (TVD)</u>	<u>Comments</u>
Uinta	Surface	
BMSW	500' MD / 500' TVD	
Garden Gulch	4,416' MD / 4,282' TVD	Oil & Associated Gas
Lower Green River*	4,561' MD / 4,427' TVD	Oil & Associated Gas
Wasatch	6,391' MD / 6,257' TVD	Oil & Associated Gas
TD	6,591' MD / 6,457' TVD	

Asterisks (*) denotes target pay intervals

All shows of fresh water and minerals will be reported and protected. A sample will be taken of any water flows and a water analysis furnished to the BLM. Oil and gas shows will be adequately tested for commercial possibilities, reported and protected by casing and cement.

2. BOP Equipment

- A) The BOPE shall be closed whenever the well is unattended. The Bureau of Land Management will be notified 24 hours prior to all BOPE pressure tests. The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
- C) As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part A:
- 1) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
 - 2) Choke Manifold
 - 3) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
 - 4) Two adjustable chokes will be used in the choke manifold.
 - 5) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
 - 6) Pressure gauges in the well control system will be designed for drilling fluid.
- D) BOPE Testing:
- 1) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
 - 2) All BOP tests will be performed with a test plug in place.
 - 3) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL

0 1,033 MD / 1, 033' TVD

1,033 MD / 1, 033' TVD – 6,591' MD / 6,457' TVD

BOP EQUIPMENT

11" Diverter with Rotating Head

3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

3. Casing and Float Equipment Program**CASING:**

Directional Well	Hole Size	OD	Depth MD/TVD	Wt.	Grade & Connection	Cond.
Surface	11"	8 5/8"	1,033 MD / 1, 033' TVD	24.0 ppf	J-55, LTC	New
Production	7 7/8"	5 1/2"	6,591' MD / 6,457' TVD	17.0 ppf	J-55, LTC	New

CASING SPECIFICATIONS:

Directional Well	Casing OD	Casing ID / Drift ID	Collapse (psi)	Int. Yield (psi)	Ten. Yield (lb)	Jt. Strength (lb)
Surface	8 5/8"	8.097" / 7.972"	1,370	2,950	381,000	244,000
Production	5 1/2"	4.492" / 4.767"	4,910	5,320	273,000	229,000

FLOAT EQUIPMENT:

SURFACE (8 5/8")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 4th joint to surface

PRODUCTION (5 1/2")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 3rd joint to 500' into surface casing**4. Cementing Programs**

CONDUCTOR (13 3/8"):

Ready Mix – Cement to surface

SURFACE (8 5/8")

Cement Top - Surface

Surface – 500'

Lead: 80 sks, Premium Lightweight Cmt w/ additives, 11.5 ppg, 2,97 cf/sk 50% excess

500' – 1,033 MD / 1, 033' TVD±

Tail: 115 sks Glass G Cement w/ additives, 15.8 ppg, 1.16 cf/sx, 50% excess

Note: The above volumes are based on a gauge-hole + 50% excess.

PRODUCTION (5 1/2")

Cement Top – 500'

500' - 4,000' TVD ±

Lead: 225 sks – Econocem Cement w/ 0.25 lbm Poly-E-Flake, 1% Granulite TR 1/4, 5 lbm Kol-Seal; 11.0 ppg; 3.54 cf/sx; 15% excess

4,000' – 6,591' MD / 6,457' TVD

Tail: 450 sks, Expandacem Cement w/ 0.25 lbm Poly-E-Flake, 1 lbm Granulite TR 1/4, 2 lbm Kol-Seal; 14.0 pp; 1.349 cf/sk; 15% excess

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
 B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
 C) The Bureau of Land Management will be notified 24 hours prior to running casing and cementing.
 D) As per 43 CFR 3160, Onshore Oil and Gas Order No.2, Drilling Operations, Part B:

- 1) All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe (minimum of 8 hours) prior to drilling out.
- 2) Prior to drilling out cement, casing will be pressure tested to 1500 psi. Pressure decline must not be greater than 10% (150 psi) in 30 minutes.
- 3) Progress reports, Form 3160-5 "Sundry Notices and Reports on Wells", shall be filed with the Field Manager within 30 days after the work is completed.
- 4) Setting of each string of casing, size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
- 5) Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.
- 6) A pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed after drilling 5-10 feet of new hole.

5. Mud Program

The proposed circulating mediums to be employed in drilling are as follows:

Interval	Mud Type	Viscosity	Fluid Loss	pH	Mud Wt. (ppg)
0 – 1,033 MD / 1, 033' TVD	Water/Spud Mud	32	No Control (NC)	7.0 -8.2	<8.8
1,033 MD / 1, 033' TVD - 6,591' MD / 6,457' TVD	DAP System	40 - 60	10 - 18	7.0-8.2	<10.0

- A) For Surface Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations. A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, filtration, and pH.
- B) The mud monitoring equipment on location will be installed by top of Green River and will be able to monitor at a minimum the pit volume totalizer (PVT), stroke counter, and flow sensor
- C) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T' and anchors.

6. Evaluation Program - Testing, Logging, and Coring

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: None anticipated.
- F) Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

7. Anticipated Pressures and H.S.

- A) The expected bottom hole pressure is 3,500 – 3,650 psig. Normal pressures are anticipated from surface to approximately TD. These pressures will be controlled by a blowout preventer stack, annular BOP, choke manifold, mud/gas separator, surface equipment and drilling mud. A supply of barite to weight the mud to a balancing specific gravity, if necessary, will be on location.
- B) Maximum expected surface pressure will be based on the frac gradient of the casing shoe. The design of the casing assumes that the MASP will be the fracture pressure at the shoe less a column of gas.
- C) No hydrogen sulfide gas is anticipated, however if H₂S is encountered, the guidelines in Onshore Oil and Gas Order No. 6 will be complied with.

8. Other Information and Notification Requirements

- A) There shall be no deviation from the proposed drilling and/or workover program as approved. Any changes in operation must have prior approval from the **Utah Division of Oil, Gas and Mining**, and the BLM Vernal (when drilling on Federal leases).
 - 1) Anticipated starting date will be upon approval. It is anticipated that completion operations will begin within 15 days after the well has been drilled.
 - 2) It is anticipated that the drilling and completion of this well will take approximately 90 days.
- B) Notification Requirements for **Utah Division of Oil, Gas and Mining**:
 - **Within 24 hrs. of spud (Carol Daniels at 801/538-5284)**
 - **24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)**

- **24 hrs. prior to cementing or testing casing (Dan Jarvis)**
- **Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)**

C) Notification Requirements BLM Vernal when drilling on Federal leases as follows: (Cade T Taylor @ cctaylor@blm.gov and [Blm ut vn opreport@blm.gov](mailto:Blm_ut_vn_opreport@blm.gov):

- **Within 24 hrs. of spud (Carol Daniels at 801/538-5284)**
- **24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)**
- **24 hrs. prior to cementing or testing casing (Dan Jarvis)**
- **Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)**

D) Any changes in the program must be approved by the **Utah Division of Oil, Gas and Mining** and or the BLM Vernal Office. "Sundry Notices and Reports on Wells" (form 3160-5) must be filed for all changes of plans. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.

1) Should the well be successfully completed for production, the BLM Pinedale Field Office must be notified when it is placed in a producing status. The notification shall provide, as a minimum, the following information items:

- Operator name, address, and telephone number.
- Well name and number.
- Well location (1/4 1/4, Section, Township, Range and P.M.)
- Date well was placed in a producing status (date of first production for which royalty will be paid).
- The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
- The Federal or Indian lease prefix and number on which the well is located. As appropriate, the unit agreement name, number and participating area name. As appropriate, the communitization agreement number.

T8S, R20E, S.L.B.&M.**ULTRA RESOURCES, INC.**


Well location, THREE RIVERS #16-36T-820,
located as shown in the SE 1/4 SE 1/4 of
Section 16, T8S, R20E, S.L.B.&M., Uintah County,
Utah.

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION
9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE,
QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD
(TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES
DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID
ELEVATION IS MARKED AS BEING 4942 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

REVISED: 02-03-14

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 11-11-13	DATE DRAWN: 01-31-14
PARTY J.F. C.K. S.S.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE ULTRA RESOURCES, INC.	

LEGEND:


- └─ = 90° SYMBOL
● = PROPOSED WELL HEAD.
▲ = SECTION CORNERS LOCATED.

NAD 83 (BOTTOM HOLE)


LATITUDE = 40°07'07.86" (40.118850)
LONGITUDE = 109°40'13.43" (109.670397)

NAD 83 (SURFACE LOCATION)

LATITUDE = 40°07'02.00" (40.117222)
LONGITUDE = 109°40'05.96" (109.668322)



RECEIVED: February 06, 2014

**LEGEND:**

 **PROPOSED LOCATION**

**ULTRA RESOURCES, INC.**

**THREE RIVERS #16-36T-820 ON EXISTING
#16-34-820 & #16-44-820 WELL PAD
SECTION 16, T8S, T20E, S.L.B.&M.
699' FSL 1311' FEL**




Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813


**ACCESS ROAD
MAP**

02 05 14
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: L.S. REVISED: 00-00-00





**LEGEND:**

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**ULTRA RESOURCES, INC.**

THREE RIVERS #16-36T-820 ON EXISTING
#16-34-820 & #16-44-820 WELL PAD
SECTION 16, T8S, T20E, S.L.B.&M.
699' FSL 1311' FEL

TOPOGRAPHIC
MAP

02 05 14
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: L.S. REVISED: 00-00-00





ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
 Field: UINTAH COUNTY Well: Three Rivers 16-36T-820
 Facility: Sec.16-T8S-R20E Wellbore: Three Rivers 16-36T-820 PWB

Targets



Name	MD (ft)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Three Rivers 16-36T-820 Target on Plat 1300' FSL & 1880' FEL		4200.00	593.00	-580.33	2152032.72	7217248.29	40°07'07.860"N	109°40'13.430"W

Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	13.00	0.000	315.619	13.00	0.00	0.00	0.00	0.00
End of Tangent	1000.00	0.000	315.619	1000.00	0.00	0.00	0.00	0.00
End of Build (S)	2100.00	22.000	315.619	2073.17	149.09	-145.90	2.00	208.60
End of Tangent (S)	3201.18	22.000	315.619	3094.17	443.91	-434.43	0.00	621.11
Drop (S)	4301.18	0.000	315.619	4167.34	593.00	-580.33	2.00	829.72
End of Tangent	6590.85	0.000	315.619	6457.00	593.00	-580.33	0.00	829.72

Location Information

Facility Name		Grid East (US R)	Grid North (US R)	Latitude	Longitude	
Sec.16-T8S-R20E		2150835.025	7217244.539	40°07'07.709"N	109°40'13.379"W	
Slot	Local N (ft)	Local E (ft)	Grid East (US R)	Grid North (US R)	Latitude	Longitude
Three Rivers 16-36T-820 (699' FSL & 1311' FEL)	-577.65	1874.80	2152032.517	7216687.358	40°07'02.809"N	109°40'05.969"W
Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mud line (At Slot: Three Rivers 16-36T-820 (699' FSL & 1311' FEL))						7897ft
Mean Sea Level to Mud line (At Slot: Three Rivers 16-36T-820 (699' FSL & 1311' FEL))						0ft
Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mean Sea Level						7897ft
Plot reference wellpath to Three Rivers 16-36T-820 PWB						
True vertical depths are referenced to Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)						
Measured depths are referenced to Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)						
Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mean Sea Level: 7897 feet						
Mean Sea Level to Mud line (At Slot: Three Rivers 16-36T-820 (699' FSL & 1311' FEL))						
Coordinates are in feet referenced to Slot						
Created by: wellbore on 2/3/2014						





Planned Wellpath Report

Three Rivers 16-36T-820 PWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 PWB
Facility	Sec.16-T8S-R20E		

REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	EWilliams
Scale	0.999911	Report Generated	2/3/2014 at 9:40:30 AM
Convergence at slot	1.17° East	Database/Source file	WellArchitectDB/Three_Rivers_16-36T-820_PWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-577.63	1974.80	2152625.02	7216667.36	40°07'02.000"N	109°40'05.960"W
Facility Reference Pt			2150639.03	7217204.54	40°07'07.709"N	109°40'31.379"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Facility Vertical Datum	7697.7
Horizontal Reference Pt	Slot	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mean Sea Level	7697.7
Vertical Reference Pt	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mud Line at Slot (Three Rivers 16-36T-820 (699' FSL & 1311' FEL))	7697.7
MD Reference Pt	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)	Section Origin	N 0.0
Field Vertical Reference	Mean Sea Level	Section Azimuth	315.6

CONFIDENTIAL



Planned Wellpath Report

Three Rivers 16-36T-820 PWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 PWB
Facility	Sec.16-T8S-R20E		

WELLPATH DATA (77 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	315.619	0.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
13.00	0.000	315.619	13.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
113.00†	0.000	315.619	113.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
120.00†	0.000	315.619	120.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	Base Gravel
213.00†	0.000	315.619	213.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
313.00†	0.000	315.619	313.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
413.00†	0.000	315.619	413.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
500.00†	0.000	315.619	500.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	BMSW
513.00†	0.000	315.619	513.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
613.00†	0.000	315.619	613.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
713.00†	0.000	315.619	713.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
813.00†	0.000	315.619	813.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
913.00†	0.000	315.619	913.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
1000.00	0.000	315.619	1000.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
1013.00†	0.260	315.619	1013.00	0.03	0.02	-0.02	40°07'02.000"N	109°40'05.960"W	2.00	
1113.00†	2.260	315.619	1112.97	2.23	1.59	-1.56	40°07'02.016"N	109°40'05.980"W	2.00	
1213.00†	4.260	315.619	1212.80	7.91	5.66	-5.54	40°07'02.056"N	109°40'06.031"W	2.00	
1313.00†	6.260	315.619	1312.38	17.08	12.21	-11.95	40°07'02.121"N	109°40'06.114"W	2.00	
1413.00†	8.260	315.619	1411.57	29.72	21.24	-20.79	40°07'02.210"N	109°40'06.228"W	2.00	
1513.00†	10.260	315.619	1510.26	45.81	32.74	-32.04	40°07'02.324"N	109°40'06.372"W	2.00	
1613.00†	12.260	315.619	1608.33	65.33	46.69	-45.70	40°07'02.461"N	109°40'06.548"W	2.00	
1713.00†	14.260	315.619	1705.66	88.27	63.09	-61.74	40°07'02.623"N	109°40'06.755"W	2.00	
1813.00†	16.260	315.619	1802.13	114.59	81.90	-80.15	40°07'02.809"N	109°40'06.992"W	2.00	
1913.00†	18.260	315.619	1897.62	144.26	103.10	-100.90	40°07'03.019"N	109°40'07.259"W	2.00	
2013.00†	20.260	315.619	1992.02	177.24	126.67	-123.97	40°07'03.252"N	109°40'07.556"W	2.00	
2100.00	22.000	315.619	2073.17	208.60	149.09	-145.90	40°07'03.473"N	109°40'07.838"W	2.00	
2113.00†	22.000	315.619	2085.22	213.47	152.57	-149.31	40°07'03.508"N	109°40'07.882"W	0.00	
2213.00†	22.000	315.619	2177.94	250.93	179.34	-175.51	40°07'03.772"N	109°40'08.219"W	0.00	
2313.00†	22.000	315.619	2270.66	288.39	206.11	-201.71	40°07'04.037"N	109°40'08.556"W	0.00	
2413.00†	22.000	315.619	2363.38	325.85	232.89	-227.91	40°07'04.301"N	109°40'08.894"W	0.00	
2513.00†	22.000	315.619	2456.10	363.32	259.66	-254.11	40°07'04.566"N	109°40'09.231"W	0.00	
2613.00†	22.000	315.619	2548.81	400.78	286.43	-280.32	40°07'04.831"N	109°40'09.568"W	0.00	
2713.00†	22.000	315.619	2641.53	438.24	313.21	-306.52	40°07'05.095"N	109°40'09.905"W	0.00	
2813.00†	22.000	315.619	2734.25	475.70	339.98	-332.72	40°07'05.360"N	109°40'10.243"W	0.00	
2913.00†	22.000	315.619	2826.97	513.16	366.75	-358.92	40°07'05.624"N	109°40'10.580"W	0.00	
3013.00†	22.000	315.619	2919.69	550.62	393.53	-385.12	40°07'05.889"N	109°40'10.917"W	0.00	
3113.00†	22.000	315.619	3012.41	588.08	420.30	-411.32	40°07'06.153"N	109°40'11.254"W	0.00	
3201.18	22.000	315.619	3094.17	621.11	443.91	-434.43	40°07'06.387"N	109°40'11.552"W	0.00	
3213.00†	21.764	315.619	3105.13	625.52	447.06	-437.51	40°07'06.418"N	109°40'11.592"W	2.00	
3313.00†	19.764	315.619	3198.63	660.97	472.39	-462.30	40°07'06.668"N	109°40'11.911"W	2.00	
3413.00†	17.764	315.619	3293.31	693.13	495.38	-484.80	40°07'06.895"N	109°40'12.200"W	2.00	
3513.00†	15.764	315.619	3389.06	721.97	515.99	-504.97	40°07'07.099"N	109°40'12.460"W	2.00	
3613.00†	13.764	315.619	3485.75	747.45	534.20	-522.79	40°07'07.279"N	109°40'12.689"W	2.00	
3713.00†	11.764	315.619	3583.28	769.55	549.99	-538.25	40°07'07.435"N	109°40'12.888"W	2.00	
3813.00†	9.764	315.619	3681.51	788.22	563.34	-551.31	40°07'07.567"N	109°40'13.056"W	2.00	



Planned Wellpath Report

Three Rivers 16-36T-820 PWP

Page 3 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 PWB
Facility	Sec.16-T8S-R20E		

WELLPATH DATA (77 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
3913.00†	7.764	315.619	3780.34	803.46	574.23	-561.96	40°07'07.675"N	109°40'13.194"W	2.00	
4013.00†	5.764	315.619	3879.64	815.23	582.65	-570.20	40°07'07.758"N	109°40'13.300"W	2.00	
4113.00†	3.764	315.619	3979.29	823.54	588.58	-576.01	40°07'07.816"N	109°40'13.374"W	2.00	
4213.00†	1.764	315.619	4079.17	828.36	592.03	-579.38	40°07'07.850"N	109°40'13.418"W	2.00	
4301.18	0.000	315.619	4167.34†	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	2.00	
4313.00†	0.000	315.619	4179.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4413.00†	0.000	315.619	4279.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4415.85†	0.000	315.619	4282.00	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	Garden Gulch
4513.00†	0.000	315.619	4379.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4560.85†	0.000	315.619	4427.00	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	Lower Green River
4613.00†	0.000	315.619	4479.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4713.00†	0.000	315.619	4579.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4813.00†	0.000	315.619	4679.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
4913.00†	0.000	315.619	4779.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5013.00†	0.000	315.619	4879.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5113.00†	0.000	315.619	4979.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5213.00†	0.000	315.619	5079.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5313.00†	0.000	315.619	5179.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5413.00†	0.000	315.619	5279.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5513.00†	0.000	315.619	5379.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5613.00†	0.000	315.619	5479.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5713.00†	0.000	315.619	5579.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5813.00†	0.000	315.619	5679.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
5913.00†	0.000	315.619	5779.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6013.00†	0.000	315.619	5879.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6113.00†	0.000	315.619	5979.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6213.00†	0.000	315.619	6079.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6313.00†	0.000	315.619	6179.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6390.85†	0.000	315.619	6257.00	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	Wasatch
6413.00†	0.000	315.619	6279.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6513.00†	0.000	315.619	6379.15	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	
6590.85	0.000	315.619	6457.00	829.72	593.00	-580.33	40°07'07.860"N	109°40'13.430"W	0.00	TD



Planned Wellpath Report

Three Rivers 16-36T-820 PWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 PWB
Facility	Sec.16-T8S-R20E		

HOLE & CASING SECTIONS - Ref Wellbore: Three Rivers 16-36T-820 PWB Ref Wellpath: Three Rivers 16-36T-820 PWP

String/Diameter	Start MD [ft]	End MD [ft]	Interval [ft]	Start TVD [ft]	End TVD [ft]	Start N/S [ft]	Start E/W [ft]	End N/S [ft]	End E/W [ft]
16in Conductor	13.00	120.00	107.00	13.00	120.00	0.00	0.00	0.00	0.00
12.25in Open Hole	120.00	1000.00	880.00	120.00	1000.00	0.00	0.00	0.00	0.00
8.625in Casing Surface	13.00	1000.00	987.00	13.00	1000.00	0.00	0.00	0.00	0.00
7.875in Open Hole	1000.00	6590.85	5590.85	1000.00	6457.00	0.00	0.00	593.00	-580.33
5.5in Casing Production	13.00	6590.85	6577.85	13.00	6457.00	0.00	0.00	593.00	-580.33

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) Three Rivers 16-36T-820 Target on Plat 1300' FSL & 1880' FEL		4200.00	593.00	-580.33	2152032.72	7217248.29	40°07'07.860"N	109°40'13.430"W	point

CONFIDENTIAL

**Planned Wellpath Report**

Three Rivers 16-36T-820 PWP

Page 5 of 5

**REFERENCE WELLPATH IDENTIFICATION**

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 PWB
Facility	Sec.16-T8S-R20E		

WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
120.00	0.000	315.619	120.00	Base Gravel
500.00	0.000	315.619	500.00	BMSW
4415.85	0.000	315.619	4282.00	Garden Gulch
4560.85	0.000	315.619	4427.00	Lower Green River
6390.85	0.000	315.619	6257.00	Wasatch
6590.85	0.000	315.619	6457.00	TD

CONFIDENTIAL

BOP Equipment

3000psi WP




EXHIBIT "F"



Ultra Resources, Inc.

March 4, 2014

Mr. Dustin Doucet
Utah Division of Oil, Gas & Mining
1594 West North Temple
Salt Lake City, Utah 84116

RE: Request for Exception to Spacing
Three Rivers 16-36T-820

Surface Location: 669' FSL & 1311' FEL, SESE, Sec. 16, T8S, R20E
Target Location: 1300' FSL & 1880' FEL, SESE, Sec. 16, T8S, R20E
SLB&M, Uintah County, Utah

Dear Mr. Doucet:

Ultra Resources respectfully submits this request for exception to spacing (Docket No. 2013-030) based on geology since the well is located less than 460 feet to the drilling unit boundary. Ultra Resources, LLC is the only owner and operator within 460 feet of the surface and target location as well as all points along the intended well bore path and are not within 460 feet of any uncommitted tracts or a unit boundary. The adjacent drilling unit boundary is covered by the same lease and has the identical production interest owners in it.


Thank you very much for your timely consideration of this application. Please feel free to contact me at 303-645-9810 should you have any questions or need additional information.

Sincerely,

A handwritten signature in blue ink, appearing to read "Debbie Ghani".

Debbie Ghani
Sr. Permitting Specialist

/dg



ULTRA RESOURCES, INC.

SITE PLAN FOR



THREE RIVERS #16-36T-820 ON EXISTING
#16-34-820 & #16-44-820 WELL PAD
SECTION 16, T8S, R20E, S.L.B.&M.
699' FSL 1311' FEL

FIGURE #1

SCALE: 1" = 60'


DATE: 01-31-14

DRAWN BY: S.S.



UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: February 06, 2014



API Number: 4304754289



Well Name: Three Rivers 16-36T-820

Township: T08.0S Range: R20.0E Section: 16 Meridian: S

Operator: ULTRA RESOURCES INC

Map Prepared: 3/6/2014
Map Produced by Diana Mason

Wells Query		Units	
Status		Status	
APD - Approved Permit		ACTIVE	
DRL - Spudded (Drilling Commenced)		EXPLORATORY	
GIW - Gas Injection		GAS STORAGE	
GS - Gas Storage		NF PP OIL	
LOC - New Location		NF SECONDARY	
OPS - Operation Suspended		PI OIL	
PA - Plugged Abandoned		PP GAS	
PGW - Producing Gas Well		PP GEOTHERML	
POW - Producing Oil Well		PP OIL	
SGW - Shut-in Gas Well		SECONDARY	
SOW - Shut-in Oil Well		TERMINATED	
TA - Temp. Abandoned			
TW - Test Well		Fields	Status
WOW - Water Disposal		Unknown	
WW - Water Injection Well		ABANDONED	
WSW - Water Supply Well		ACTIVE	
		COMBINED	
		INACTIVE	
		STORAGE	
		TERMINATED	



Well Name	ULTRA RESOURCES INC Three Rivers 16-36T-820 43047542890000			
String	SURF	PROD		
Casing Size(in)	8.625	5.500		
Setting Depth (TVD)	1033	6457		
Previous Shoe Setting Depth (TVD)	0	1033		
Max Mud Weight (ppg)	8.8	10.0		
BOPE Proposed (psi)	1000	3000		
Casing Internal Yield (psi)	2950	5320		
Operators Max Anticipated Pressure (psi)	3500	10.4		

Calculations	SURF String	8.625	"	
Max BHP (psi)	.052*Setting Depth*MW=	473		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	349	YES	diverter with rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	246	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	246	NO	OK
Required Casing/BOPE Test Pressure=		1033	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient	


Calculations	PROD String	5.500	"	
Max BHP (psi)	.052*Setting Depth*MW=	3358		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2583	YES	3M BOP, dbl ram, annular with diverter and rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1937	YES	Ok
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2165	NO	OK
Required Casing/BOPE Test Pressure=		3000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		1033	psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

43047542890000 Three Rivers 16-36T-820

Casing Schematic



✓ Stop cuts

Uinta

to 0' @ 8% w/o, tail 633

TOC @ 206

400' ± BMSW

300' BMSW (ultra)

714' tail

* Stop ✓

Surface

1000. MD

1000. TVD

TOC @ 1176

to 424' @ 8% w/o, tail 3944'

* Proposed to 500'

4248' tail (Proposed to 4000')

4282' Garden Gulch

4427' Lower Green River

* Stop ✓

6257' Wasatch

Production

6591. MD

6457. TVD

699 SL

593

1292 FSL

1311 EL

-580

1891 FEL

OK

SW SE Sec 16-85-20E

Well name:	43047542890000 Three Rivers 16-36T-820	
Operator:	ULTRA RESOURCES INC	
String type:	Surface	Project ID: 43-047-54289
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.800 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 206 ft

Burst

Max anticipated surface pressure: 880 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 868 ft

Completion type is subs
Non-directional string.

Re subsequent strings:

Next setting depth: 6,457 ft
Next mud weight: 10.000 ppg
Next setting BHP: 3,354 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,000 ft
Injection pressure: 1,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1000	8.625	24.00	J-55	ST&C	1000	1000	7.972	5148
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	457	1370	2.997	1000	2950	2.95	20.8	244	11.71 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 3, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1000 ft, a mud weight of 8.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43047542890000 Three Rivers 16-36T-820	
Operator:	ULTRA RESOURCES INC	
String type:	Production	Project ID: 43-047-54289
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 10.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 164 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 1,176 ft

Burst

Max anticipated surface pressure: 1,934 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,354 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 5,612 ft

Completion type is subs

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 830 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	6591	5.5	17.00	J-55	LT&C	6457	6591	4.767	25535
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3354	4910	1.464	3354	5320	1.59	109.8	247	2.25 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 3, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6457 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



Diana Mason <dianawhitney@utah.gov>

APD Approval

Jeff Conley <jconley@utah.gov>

Tue, Apr 15, 2014 at 8:42 AM

To: Diana Mason <dianawhitney@utah.gov>, Bradley Hill <bradhill@utah.gov>

Cc: Jim Davis <jimdavis1@utah.gov>, starpoint <starpoint@etv.net>

Hello,

The following well has been approved by SITLA including arch and paleo:

(4304754289) Three Rivers 16-36T-820

Thank you,

Jeff Conley
SITLA Resource Specialist
jconley@utah.gov
801-538-5157

CONFIDENTIAL

RECEIVED: April 15, 2014

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator ULTRA RESOURCES INC
Well Name Three Rivers 16-36T-820
API Number 43047542890000 **APD No** 9389 **Field/Unit** THREE RIVERS
Location: 1/4,1/4 SESE **Sec** 16 **Tw** 8.0S **Rng** 20.0E 699 FSL 1311 FEL
GPS Coord (UTM) 613481 4441629 **Surface Owner**

Participants

Jim Burns (permit contractor), Ben Williams (DWR), Jim Davis (SITLA), Bart Hunting (surveyor), Richard Powell (UDOGM)

Regional/Local Setting & Topography

This proposed well sits on an existing well location. It is located approximately midway between the Green River bridge in Ouray to the south and Pelican Lake to the north and sits less than a half mile west of highway 88.

Surface Use Plan

Current Surface Use
Existing Well Pad

New Road Miles	Well Pad	Src Const Material	Surface Formation
0	Width 257' Length 405'	Offsite	ALLU

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands

Flora / Fauna

Antelope habitat, high desert vegetation with small sage and sparse desert grasses

Soil Type and Characteristics

Sandy loam

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diversion Required?

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run? Paleo Potential Observed? Cultural Survey Run? Cultural Resources?

Reserve Pit

Site-Specific Factors

Site Ranking

**Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits**

Final Score

Sensitivity Level

Characteristics / Requirements

Existing reserve pit will be used. Liner appears to be in good condition.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

Richard Powell
Evaluator

3/6/2014
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
9389	43047542890000	LOCKED	OW	S	No
Operator	ULTRA RESOURCES INC		Surface Owner-APD		
Well Name	Three Rivers 16-36T-820		Unit		
Field	THREE RIVERS		Type of Work	DRILL	
Location	SESE 16 8S 20E S 699 FSL 1311 FEL GPS Coord (UTM) 613483E 4441616N				

Geologic Statement of Basis

Ultra proposes to set 1,033 feet of surface pipe, cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at approximately 400 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation and alluvium derived from the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

3/17/2014
Date / Time

Surface Statement of Basis

This proposed well is to be placed on an existing oil well location. The surface and minerals are controlled by SITLA. SITLA representative Jim Davis was in attendance for this presite and stated that he no concerns with the placement of this additional well and that the condition of the existing well pad is acceptable to SITLA. Ben Williams of the Utah DWR also attended this inspection and stated that this area is antelope habitat but made no recommendations regarding wildlife for this site. The existing reserve pit liner appears to be in good condition and appears acceptable for use for the additional drilling activities. An additional 40 feet is proposed for the north end of the location. It appears this addition will cause not problems and no concerns were voiced concerning this change.

Richard Powell
Onsite Evaluator

3/6/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 2/6/2014

API NO. ASSIGNED: 43047542890000

WELL NAME: Three Rivers 16-36T-820

OPERATOR: ULTRA RESOURCES INC (N4045)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SESE 16 080S 200E

Permit Tech Review: ☒

SURFACE: 0699 FSL 1311 FEL

Engineering Review: ☒

BOTTOM: 1300 FSL 1880 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.11721

LONGITUDE: -109.66828

UTM SURF EASTINGS: 613483.00

NORTHINGS: 4441616.00

FIELD NAME: THREE RIVERS

LEASE TYPE: 3 - State

LEASE NUMBER: ML-49319

PROPOSED PRODUCING FORMATION(S): GREEN RIVER - LOWER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: STATE - 022046398
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 49-2262
- ☐ RDCC Review:
- ☐ Fee Surface Agreement
- ☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: Cause 270-02
- Effective Date: 11/9/2013
- Siting: (2) Wells Per Drilling Unit
- ☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
12 - Cement Volume (3) - hmadonald
15 - Directional - dmason
25 - Surface Casing - hmadonald

RECEIVED: April 15, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Three Rivers 16-36T-820

API Well Number: 43047542890000

Lease Number: ML-49319

Surface Owner: STATE

Approval Date: 4/15/2014

Issued to:

ULTRA RESOURCES INC, 304 Inverness Way South #245, Englewood, CO 80112

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 270-02. The expected producing formation or pool is the GREEN RIVER - LOWER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R. 649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2" production string shall be determined from actual hole diameter in order to place lead cement from the pipe setting depth back to 500' MD as indicated in the submitted drilling plan and the tail cement to 500' above the Garden Gulch.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #245 , Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 16-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0699 FSL 1311 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047542890000
PHONE NUMBER: 303 645-9810 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 5/28/2014	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Ultra Resources will be moving in ProPetro to spud the Three Rivers 16-36T-820 (API# 43-047-54289) on 5/28/2014. Any question please call Bryan Coltharp 307-713-5522		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 28, 2014		
NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 5/28/2014	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 16-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0699 FSL 1311 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047542890000
PHONE NUMBER: 303 645-9810 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 7/7/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Monthly status report of drilling and completion attached.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 11, 2014		
NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 7/7/2014	

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/01/2014

WELL NAME

THREE RIVERS 16-36T-820

AFE#

140618

SPUD DATE

06/16/2014

WELL SITE CONSULTANT

JEREMY MEJORADO

PHONE#

435-219-4933

CONTRACTOR

Other

TD AT REPORT

(no data)

FOOTAGE

PRATE

CUM. DRLG. HRS

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

6,511'

PRESENT OPS

(nothing recorded)

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

NEXT CASING DEPTH

SSE

SSED

TIME BREAKDOWN

RIG UP / TEAR DOWN 1.50

DETAILS

Start	End	Hrs	
05:00	06:30	01:30	MOVE IN AND RIG UP

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

LL/BP Received Today:

RECENT CASINGS RUN:		Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg		
Surface		06/01/2014	8 5/8	J-55	24	1,040				
Conductor		05/28/2014	16	ARJ-55	45	101				

RECENT BITS:		MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
BIT	SIZE									

BIT OPERATIONS:		RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
BIT	WOB										

RECENT MUD MOTORS:		MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
#	SIZE								

MUD MOTOR OPERATIONS:		REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
#	WOB							

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads	23,310	23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	315	315	10,000
8100..320: Mud & Chemicals			55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	31,040	31,040	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel			20,000	8100..410: Mob/Demob			
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/			1,000	8100..520: Trucking & Hauling	700	700	23,000
8100..530: Equipment Rental			17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			10,000	8100..535: Directional Drillin			65,000
8100..540: Fishing				8100..600: Surface Casing/Inte	1,596	19,309	35,000
8100..605: Cementing Work	19,510	19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies				8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing			50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	76,471	94,184	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/14/2014

WELL NAME

THREE RIVERS 16-36T-820

AFE#

140618

SPUD DATE

06/16/2014

WELL SITE CONSULTANT

JEREMY MEJORADO

PHONE#

435-219-4933

CONTRACTOR

Other

TD AT REPORT

(no data)

FOOTAGE

PRATE

CUM. DRLG. HRS

7.5

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

6,511'

PRESENT OPS

(nothing recorded)

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

NEXT CASING DEPTH

SSE

SSD

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

LL/BP Received Today:

RECENT CASINGS RUN:			Date Set		Size	Grade	Weight	Depth	FIT Depth		FIT ppg	
Surface			06/01/2014		8 5/8	J-55	24	1,040				
Conductor			05/28/2014		16	ARJ-55	45	101				
RECENT BITS:												
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS		TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		
BIT OPERATIONS:												
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
RECENT MUD MOTORS:												
#	SIZE	MANUF	TYPE		SERIAL NO.	LOBES		DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
MUD MOTOR OPERATIONS:												
#	WOB	REV/GAL	HRS		24hr DIST	24HR ROP		CUM HRS	CUM DIST	CUM ROP		
SURVEYS												
Date	TMD	Incl	Azimuth		TVD	VS	NS	EW	DLS	Tool Type		

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		315	10,000
8100..320: Mud & Chemicals			55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig		31,040	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel			20,000	8100..410: Mob/Demob			
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/			1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental			17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			10,000	8100..535: Directional Drillin			65,000
8100..540: Fishing				8100..600: Surface Casing/Inte		19,309	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies				8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing			50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost		94,184	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/15/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618		SPUD DATE	06/16/2014	
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933		CONTRACTOR	Other	
TD AT REPORT	1,555'	FOOTAGE	495'	PRATE	CUM. DRLG. HRS 7.5		DRLG DAYS SINCE SPUD	0	
ANTICIPATED TD	6,511'	PRESENT OPS	Drilling at 1,555'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	DH:		CUM. MUD LOSS		SURF:	DH:		
MUD COMPANY:				MUD ENGINEER:					
LAST BOP TEST	NEXT CASING SIZE		5 1/2	NEXT CASING DEPTH		6,525	SSE	0	SSD 0

AFE Days vs Depth:

DWOP Days vs Depth:

AFE Cost Vs Depth:

LL/BP Received Today:

RECENT CASINGS RUN:			Date Set		Size	Grade	Weight	Depth	FIT Depth		FIT ppg	
Surface			06/01/2014		8 5/8	J-55	24	1,040				
Conductor			05/28/2014		16	ARJ-55	45	101				
RECENT BITS:												
BIT	SIZE	MANUF	TYPE	SERIAL NO.		JETS		TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
BIT OPERATIONS:												
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
RECENT MUD MOTORS:												
#	SIZE	MANUF	TYPE		SERIAL NO.		LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
MUD MOTOR OPERATIONS:												
#	WOB	REV/GAL	HRS		24hr DIST		24HR ROP	CUM HRS	CUM DIST	CUM ROP		
SURVEYS												
Date	TMD	Incl	Azimuth		TVD	VS	NS	EW	DLS	Tool Type		

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		315	10,000
8100..320: Mud & Chemicals			55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig		31,040	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel			20,000	8100..410: Mob/Demob			
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/			1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental			17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			10,000	8100..535: Directional Drillin			65,000
8100..540: Fishing				8100..600: Surface Casing/Inte		19,309	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies				8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing			50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost		94,184	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/16/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618	SPUD DATE	06/16/2014		
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933	CONTRACTOR	Ensign 122		
TD AT REPORT	1,555'	FOOTAGE	495'	PRATE	82.5	CUM. DRLG. HRS	13.5	DRLG DAYS SINCE SPUD	0
ANTICIPATED TD	6,511'	PRESENT OPS	Drilling at 1,555'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	0	DH:	0	CUM. MUD LOSS	SURF:	0	DH:	0
MUD COMPANY:	NEW PARK			MUD ENGINEER:	EDGER CLOY				
LAST BOP TEST	06/16/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	6,525	SSE	0	SSED	0

TIME BREAKDOWN									
DIRECTIONAL DRILLING		4.00	DRILLING		2.00	DRILLING CEMENT		1.00	
NIPPLE UP B.O.P.		2.00	PRESSURE TEST B.O.P.		4.50	RIG MOVE		1.00	
RIG SERVICE		0.50	RIG UP / TEAR DOWN		5.00	WORK BHA		1.00	

DETAILS				
Start	End	Hrs		
09:00	10:00	01:00	SKID RIG WITH RW JONES TRUCKING	
10:00	15:00	05:00	RIG UP ELECTRICAL SKIDS, FLOWLINE, MUD LINE, WATER LINES & HYDRAULIC LINES	
15:00	17:00	02:00	NIPPLE UP BOP AND CHOKE LINE	
17:00	21:30	04:30	SAFETY MEETING - RIG UP TESTER (B&C QUICK TEST) AND TEST TEST BOP (PIPE RAMS, BLIND RAMS, CHOKE LINE & CHOKE VALVES, FOSV, INSIDE BOP, KILL LINE AND VALVES, CHOKE MANIFOLD, HCR & MANUAL VALVE ALL @ 10 MIN 3000 PSI HIGH 10 MIN 250 PSI LOW - ANNULAR @ 10 MIN 1500 PSI HIGH 10 MIN 250 PSI LOW - CASING @ 30 MIN 1500 PSI - RIG DOWN TESTER	
21:30	22:30	01:00	DIRECTIONAL WORK - PICK UP MUD MOTOR, MAKE UP BIT - PICK UP DIRECTIONAL TOOLS - LOAD MWD TOOL AND TEST	
22:30	23:00	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, CATWALK, ROUGHNECK & PILLAR BLOCKS - CHECK OIL LEVEL ON ALL PUMPS AND MOTORS	
23:00	01:00	02:00	T.I.H. FROM 98' TO 940' - INSTALL ROTATING HEAD (TAG CEMENT @ 940')	
01:00	02:00	01:00	TAG CEMENT @ 940' - DRILL CEMENT, PLUG, FLOAT COLLAR & SHOE WITH 310 GPM, 25 RPM, 5-8K WOB	
02:00	06:00	04:00	DIRECTIONAL DRILLING FROM 1060' TO 1555' (495')123.8 FT/HR GPM=500, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1520 PSI, DIFF PRESSURE=250-550 PSI, WOB=22K, TQ=8500K, MUD WT 9.3, VIS 32	
05:55	05:55	00:00	SAFETY MEETING DAYS:RIG SKID/RIGGING UP/TESTING BOP SAFETY MEETING NIGHTS:TESTING BOP/PICKING UP TOOLS/TRIPPING PIPE REGULATORY NOTICES: NONE. REGULATORY VISITS:NONE. INCIDENTS:NONE. SAFETY DRILLS:NONE.	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	530.0	3,750.0		3,220.0	530.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	06/01/2014	8 5/8	J-55	24	1,040		
Conductor	05/28/2014	16	ARJ-55	45	101		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	SECURITY	MM55M	12450966	12/12/12/12/12	0.552	1,060		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		55/120	440	2,100	2.96	4.00	495	123.75	4.00	495	123.75

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	ENSIGN	FBH	650-056	7/8	1,060		06/15/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	22	0.24	4.00	495	123.75	4.00	495	123.75			

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	
06/16/2014	1,279	1.1	148.70	1,370	-4.9	-6.54	0.06	1.5	MWD Survey Tool	
06/16/2014	1,188	2.3	172.90	1,279	-2.6	-3.98	-0.62	1.2	MWD Survey Tool	
06/16/2014	1,097	1.8	201.30	1,188	-0.4	-0.83	-0.33	3.2	MWD Survey Tool	

MUD PROPERTIES										
Type	LSND	Mud Wt	9.3	Alk.		Sand %		XS Lime lb/bbl		
Temp.	90	Gels 10sec	3	Cl ppm	2,800	Solids %	7.0	Salt bbls		
Visc	33	Gels 10min	5	Ca ppm	120	LGS %	7.0	LCM ppb		
PV	10	pH	11.5	pF	0.8	Oil %		API WL cc	12.0	
YP	5	Filter Cake/32	2	Mf	1.7	Water %	93.0	HTHP WL cc		
O/W Ratio		ES		WPS						
Comments: ENGINEER=1										
Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0				

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION											
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	70	PSI	1,520	GPM	500	SPR	Slow PSI
Pump 2 Liner	6.5	Stroke Len	9.0	SPM	70	PSI	1,520	GPM		SPR	Slow PSI
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	Slow PSI
BHA Makeup								Length	921.4		Hours on BHA
Up Weight	67	Dn Weight	45	RT Weight	57			Torque	8,500		Hours on Motor

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	BIT	7.875	0.000	1.00		12450966	SECURITY MM55M
2	MUD MOTOR	6.500	0.000	32.00		650113	1.5 DEG FBH 7/8 5.7 .24
3	MONEL	6.500	3.250	30.61		EN122-2	4.5 XO B X P
4	GAP SUB	6.500	3.250	5.49		650-001	4.5 XO BXP
5	MONEL	6.500	2.813	30.28		EN0815-12	
6	MONEL	6.500	2.813	30.22		EN0814-12	
7	DC	6.500	2.250	31.06		RIG	
8	(18) HWDP	4.500	2.313	547.01		RIG	
9	DRILLING JAR	6.500	2.813	31.68		67029E	
10	(6) HWDP	4.500	2.313	182.09		RIG	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		315	10,000
8100..320: Mud & Chemicals	2,100	2,100	55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	16,538	47,578	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel			20,000	8100..410: Mob/Demob			
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/	1,610	1,610	1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental	320	320	17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			10,000	8100..535: Directional Drillin	14,500	14,500	65,000
8100..540: Fishing				8100..600: Surface Casing/Inte		19,309	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	2,500	2,500	35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	4,132	4,132		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing	79,855	79,855	50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	121,555	215,738	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/17/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618		SPUD DATE	06/16/2014		
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933		CONTRACTOR	Ensign 122		
TD AT REPORT	4,137'	FOOTAGE	2,582'	PRATE	112.3	CUM. DRLG. HRS	36.5	DRLG DAYS SINCE SPUD	1	
ANTICIPATED TD	6,511'	PRESENT OPS			Drilling at 4,137'		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	20	DH:	125	CUM. MUD LOSS	SURF:	20	DH:	125	
MUD COMPANY:	NEW PARK			MUD ENGINEER:			EDGER CLOY			
LAST BOP TEST	06/17/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,480	SSE	0	SSED	0

TIME BREAKDOWN									
COND MUD & CIRCULATE	0.50			DIRECTIONAL DRILLING	23.00			RIG SERVICE	0.50

DETAILS			
Start	End	Hrs	
06:00	12:00	06:00	DIRECTIONAL DRILLING FROM 1555' TO 2416' (860')143.3 FT/HR GPM=500, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1750 PSI, DIFF PRESSURE=250-550 PSI, WOB=22K, TQ=8500K, MUD WT 9.3, VIS 32
12:00	12:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, CATWALK, ROUGHNECK & PILLAR BLOCKS - CHECK OIL LEVEL ON ALL PUMPS AND MOTORS
12:30	04:30	16:00	DIRECTIONAL DRILLING FROM 2416' TO 4091' (1675')104.7 FT/HR GPM=440, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1650 PSI, DIFF PRESSURE=250-550 PSI, WOB=24K, TQ=9500 FT/LBS, MUD WT 9.3, VIS 40
04:30	05:00	00:30	WORK STUCK PIPE - PUMP 20 BBL HIGH VIS SWEEP - CIRCULATE HOLE CLEAN - RESUME DRILLING
05:00	06:00	01:00	DIRECTIONAL DRILLING FROM 4091' TO 4137' (46')46 FT/HR GPM=440, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1650 PSI, DIFF PRESSURE=250-550 PSI, WOB=22K, TQ=10000 FT/LBS, MUD WT 9.3, VIS 42
05:55	05:55	00:00	SAFETY MEETING DAYS:LAST DAY STAY FOCUSED/TRIP HAZARDS SAFETY MEETING NIGHTS:LAST NIGHT STAY FOCUSED/TRIP HAZARDS REGULATORY NOTICES: NONE. REGULATORY VISITS:NONE. INCIDENTS:NONE. SAFETY DRILLS:BOP DRILL DAY & NIGHTS CREWS READY IN 35 SEC

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,470.0	0.0	0.0	1,750.0	2,000.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	06/01/2014	8 5/8	J-55	24	1,040		
Conductor	05/28/2014	16	ARJ-55	45	101		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
1	7.875	SECURITY	MM55M	12450966	12/12/12/12/12	0.552	1,060		-----

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		55/106	440	1,650	2.96	23.00	2,582	112.26	27.00	3,077	113.96

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	ENSIGN	FBH	650-056	7/8	1,060		06/15/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	24	0.24	23.00	2,582	112.26	27.00	3,077	113.96			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
06/17/2014	3,996	12.4	320.50	3,936	804.9	593.41	-543.82	2.4	MWD Survey Tool		
06/17/2014	3,905	14.6	320.10	3,848	783.6	577.07	-530.25	2.4	MWD Survey Tool		
06/17/2014	3,815	16.7	319.30	3,761	759.4	558.56	-514.54	0.9	MWD Survey Tool		

MUD PROPERTIES										
Type	LSND	Mud Wt	9.3	Alk.		Sand %		XS Lime lb/bbl		
Temp.	95	Gels 10sec	3	Cl ppm	5,600	Solids %	6.5	Salt bbls		
Visc	38	Gels 10min	5	Ca ppm	120	LGS %	6.5	LCM ppb		
PV	10	pH	10.5	pF	0.7	Oil %		API WL cc	12.0	
YP	9	Filter Cake/32	2	Mf	1.6	Water %	93.0	HTHP WL cc		
O/W Ratio		ES		WPS						
Comments:	DYNA FIBER=12, ENGINEER=1, EVOTROL=1, EXWATE=120, LIME=6, MONOETHANOLAMINE=1, NEWCARB=11, NEWGEL=26, NEWPAC R=6, NEWPHPA=4, NEWZAN D=6, PALLETS=16, POTASSIUM HYDROXIDE=1, SAWDUST=20, SHRINKWRAP=15									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION											
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	1,650	GPM	440	SPR	Slow PSI
Pump 2 Liner	6.5	Stroke Len	9.0	SPM	70	PSI	1,520	GPM		SPR	Slow PSI
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	Slow PSI
BHA Makeup								Length	921.4		Hours on BHA
Up Weight	115	Dn Weight	85	RT Weight	98			Torque	10,000		Hours on Motor

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	BIT	7.875	0.000	1.00		12450966	SECURITY MM55M
2	MUD MOTOR	6.500	0.000	32.00		650113	1.5 DEG FBH 7/8 5.7 .24
3	MONEL	6.500	3.250	30.61		EN122-2	4.5 XO B X P
4	GAP SUB	6.500	3.250	5.49		650-001	4.5 XO BXP
5	MONEL	6.500	2.813	30.28		EN0815-12	
6	MONEL	6.500	2.813	30.22		EN0814-12	
7	DC	6.500	2.250	31.06		RIG	
8	(18) HWDP	4.500	2.313	547.01		RIG	
9	DRILLING JAR	6.500	2.813	31.68		67029E	
10	(6) HWDP	4.500	2.313	182.09		RIG	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		315	10,000
8100..320: Mud & Chemicals	7,682	9,782	55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	19,425	67,003	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel			20,000	8100..410: Mob/Demob			
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/		1,610	1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental	2,650	2,970	17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	650	650	10,000	8100..535: Directional Drillin	8,500	23,000	65,000
8100..540: Fishing				8100..600: Surface Casing/Inte	255	19,564	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	2,500	5,000	35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	4,990	9,122		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing	3,703	83,558	50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	50,355	266,093	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/18/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618		SPUD DATE	06/16/2014		
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933		CONTRACTOR	Ensign 122		
TD AT REPORT	6.356'	FOOTAGE	2.219'	PRATE	94.4	CUM. DRLG. HRS	60.0	DRLG DAYS SINCE SPUD	2	
ANTICIPATED TD	6.511'	PRESENT OPS			Drilling at 6.356'		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	0	DH:	180	CUM. MUD LOSS	SURF:	20	DH:	305	
MUD COMPANY:	NEW PARK			MUD ENGINEER:			EDGER CLOY			
LAST BOP TEST	06/18/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,490	SSE	0	SSD	0

TIME BREAKDOWN			
DIRECTIONAL DRILLING	23.50	RIG SERVICE	0.50

DETAILS				
Start	End	Hrs		
06:00	12:30	06:30	DIRECTIONAL DRILLING FROM 4137' TO 4680' (83.5')46 FT/HR GPM=440, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1650 PSI, DIFF PRESSURE=250-550 PSI, WOB=24K, TQ=10000 FT/LBS, MUD WT 9.3, VIS 42	
12:30	13:00	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, CATWALK, ROUGHNECK & PILLAR BLOCKS - CHECK OIL LEVEL ON ALL PUMPS AND MOTORS	
13:00	06:00	17:00	DIRECTIONAL DRILLING FROM 4680' TO 6356' (1676')98.6 FT/HR GPM=440, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1850 PSI, DIFF PRESSURE=250-550 PSI, WOB=26K, TQ=12000 FT/LBS, MUD WT 9.6, VIS 42	
05:55	05:55	00:00	SAFETY MEETING DAYS:FIRST DAY BACK/MAKING CONNECTIONS/BOP DUTIES SAFETY MEETING NIGHTS:FIRST DAY BACK/MAKING CONNECTIONS REGULATORY NOTICES: NONE. REGULATORY VISITS:NONE. INCIDENTS:NONE. SAFETY DRILLS:NONE	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,400.0	3,500.0		3,850.0	3,400.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	06/01/2014	8 5/8	J-55	24	1,040		
Conductor	05/28/2014	16	ARJ-55	45	101		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	SECURITY	MM55M	12450966	12/12/12/12/12	0.552	1,060		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		55/106	440	1,850	3.05	23.50	2,219	94.43	50.50	5,296	104.87

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	ENSIGN	FBH	650-056	7/8	1,060		06/15/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	26	0.24	23.50	2,219	94.43	50.50	5,296	104.87			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
06/18/2014	6,170	1.1	183.00	6,106	853.4	615.17	-592.23	0.5	MWD Survey Tool		
06/18/2014	6,079	1.4	195.80	6,015	854.6	617.11	-591.88	0.1	MWD Survey Tool		
06/18/2014	5,989	1.3	198.20	5,925	855.7	619.14	-591.26	0.3	MWD Survey Tool		

MUD PROPERTIES											
Type	LSND	Mud Wt	9.6	Alk.		Sand %		XS Lime lb/bbl			
Temp.	100	Gels 10sec	6	Cl ppm	5,000	Solids %	9.1	Salt bbls			
Visc	42	Gels 10min	8	Ca ppm	80	LGS %	9.1	LCM ppb			
PV	14	pH	10.0	pF	1.0	Oil %		API WL cc	7.2		
YP	10	Filter Cake/32	2	Mf	2.0	Water %	90.0	HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	BUSAN=1, DYNA FIBER=21, ENGINEER=1, EVOTROL=7, EXWATE=120, EVOLUBE=1, GSX=12, NEWCARB=21, NEWGEL=16, NEWPHALT=5, NEWPAC R=5, NEWPHPA=5, NEWZAN D=8, POTASSIUM HYDROXIDE=2, SAWDUST=50, WALNUT=7										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION											
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	1,850	GPM	440	SPR	Slow PSI
Pump 2 Liner	6.5	Stroke Len	9.0	SPM	0	PSI	0	GPM		SPR	Slow PSI
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	Slow PSI
BHA Makeup								Length	921.4		Hours on BHA
Up Weight	160	Dn Weight	95	RT Weight	125			Torque	12,500		Hours on Motor

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	BIT	7.875	0.000	1.00		12450966	SECURITY MM55M
2	MUD MOTOR	6.500	0.000	32.00		650113	1.5 DEG FBH 7/8 5.7 .24
3	MONEL	6.500	3.250	30.61		EN122-2	4.5 XO B X P
4	GAP SUB	6.500	3.250	5.49		650-001	4.5 XO BXP
5	MONEL	6.500	2.813	30.28		EN0815-12	
6	MONEL	6.500	2.813	30.22		EN0814-12	
7	DC	6.500	2.250	31.06		RIG	
8	(18) HWDP	4.500	2.313	547.01		RIG	
9	DRILLING JAR	6.500	2.813	31.68		67029E	
10	(6) HWDP	4.500	2.313	182.09		RIG	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	683	998	10,000
8100..320: Mud & Chemicals	10,621	20,403	55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	19,425	86,428	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel	11,027	11,027	20,000	8100..410: Mob/Demob	2,000	2,000	
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services			4,000
8100..510: Testing/Inspection/		1,610	1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental	2,650	5,620	17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	650	1,300	10,000	8100..535: Directional Drillin	8,500	31,500	65,000
8100..540: Fishing				8100..600: Surface Casing/Inte		19,564	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole			14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	2,500	7,500	35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	6,386	15,508		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing		83,558	50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	64,442	330,536	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/19/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618	SPUD DATE	06/16/2014		
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933	CONTRACTOR	Ensign 122		
TD AT REPORT	6,499'	FOOTAGE	143'	PRATE	71.5	CUM. DRLG. HRS	62.0	DRLG DAYS SINCE SPUD	3
ANTICIPATED TD	6,511'	PRESENT OPS	Cement Production Casing at 6,499'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	10	DH:	202	CUM. MUD LOSS	SURF:	30	DH:	507
MUD COMPANY:	NEW PARK			MUD ENGINEER:	PAUL SCANION				
LAST BOP TEST	06/19/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	6,491	SSE	0	SSED	0

TIME BREAKDOWN	CASING & CEMENT	7.50	COND MUD & CIRCULATE	2.50	DIRECTIONAL DRILLING	2.00
	TRIPPING	6.00	WIRELINE	5.00	WORK BHA	1.00

DETAILS	Start	End	Hrs	
	06:00	08:00	02:00	DIRECTIONAL DRILLING FROM 6356' TO 6499' (143')71.5 FT/HR GPM=440, TOP DRIVE RPM=50, MOTOR RPM=120, TOTAL RPM=170, OFF BOTTOM PRESSURE=1950 PSI, DIFF PRESSURE=250-550 PSI, WOB=26K, TQ=12000 FT/LBS, MUD WT 9.6, VIS 42 (TD @ 8 AM 6/18/14)
	08:00	09:00	01:00	CIRCULATE HOLE CLEAN - PUMP TWO HIGH VIS SWEEPS
	09:00	15:00	06:00	T.O.O.H. F/6499' T/98' - PUMP AND ROTATE OUT FROM 6499' T/5600'
	15:00	16:00	01:00	DIRECTIONAL WORK - LAY DOWN DIRECTIONAL; TOOLS - BREAK BIT - DRAIN MUD MOTOR AND LAY DOWN SAME
	16:00	21:00	05:00	RIG UP LOGGERS & LOG WELL (LOGGERS DEPTH=6474')- RIG DOWN LOGGERS
	21:00	02:30	05:30	RIG UP TO RUN 5.5" CASING - RUN 148 JOINTS 5.5" 17# J-55 CASING WITH 2 MARKER JOINTS (5207', 4364') AND 44 CENTRALIZERS - CASING SET @ 6487'
	02:30	04:00	01:30	CIRCULATE AND CONDITION MUD FOR CEMENT JOB
	04:00	06:00	02:00	SAFETY MEETING WITH HALLIBURTON - RIG UP CEMENTERS - TEST LINES TO 5000 PSI - PUMP 10 BBLS WATER SPACER, 20 BBLS 10.0 PPG SUPER FLUSH, 10 BBLS WATER SPACER, 146 BBLS 235 SACKS 11 PPG 3.5 YIELD LEAD CEMENT MIXED @ 20.92 GAL/SK, 96 BBLS 400 SKS 14 PPG 1.35 YIELD TAIL CEMENT MIXED @ 5.82 GAL/SK, SHUT DOWN WASH LINES DROP PLUG AND DISPLACE WITH 150.5 BBLS FRESH WATER - FINAL CIRCULATING PRESSURE 1350PSI BUMP PLUG AND HOLD 2000 PSI FOR TWO MINUTES - RELEASE PRESSURE FLOATS HELD - 3/4 TO FULL RETURNS DURING JOB 0 BBLS CEMENT TO SURFACE
	05:55	05:55	00:00	SAFETY MEETING DAYS:TRIPPING PIPE/LOGGING SAFETY MEETING NIGHTS:LOGGING/RUNNING CSG/CEMENTING REGULATORY NOTICES: BOP TEST NOTICE FOR THE 16-44-820 SENT @ 1930 6/18/14 REGULATORY VISITS:NONE. INCIDENTS:NONE. SAFETY DRILLS:NONE

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE	Fluid	Used	Received	Transferred	On Hand	Cum.Used
	Fuel	980.0	0.0	0.0	2,870.0	4,380.0
	Gas					
	Fresh Well Water					
	Nano Water					
	Frac Water					
	Reserve Pit Water					
	Boiler Hours					
	Air Heater Hours					
	Urea				0.0	
	Urea Sys 1 Hrs					
	Urea Sys 2 Hrs					
	Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	06/19/2014	5 1/2	J-55	17	6,487		
Surface	06/01/2014	8 5/8	J-55	24	1,040		
Conductor	05/28/2014	16	ARJ-55	45	101		

RECENT BITS:	BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
	1	7.875	SECURITY	MM55M	12450966	12/12/12/12/12	0.552	1,060	6,499	1-1-WT-S-X-X--TD

BIT OPERATIONS:	BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	1		55/106	440	1,850	3.05	2.00	143	71.50	52.50	5,439	103.60

RECENT MUD MOTORS:	#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
	1	6.500	ENSIGN	FBH	650-056	7/8	1,060	6,499	06/15/2014	06/18/2014

MUD MOTOR OPERATIONS:	#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	1	26	0.24	2.00	143	71.50	52.50	5,439	103.60

SURVEYS	Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
	06/19/2014	6,499	1.1	182.70	6,435	849.3	609.20	-592.77	0.0	MWD Survey Tool
	06/19/2014	6,499	1.1	182.70	6,435	849.3	609.20	-592.77		MWD Survey Tool
	06/19/2014	6,442	1.1	182.70	6,378	850.1	610.29	-592.72	0.1	MWD Survey Tool

MUD PROPERTIES	Type	LSND	Mud Wt	9.6	Alk.		Sand %		XS Lime lb/bbl	
	Temp.	100	Gels 10sec	6	Cl ppm	5,000	Solids %	9.0	Salt bbls	
	Visc	43	Gels 10min	9	Ca ppm	80	LGS %	9.0	LCM ppb	
	PV	15	pH	10.0	pF	1.0	Oil %		API WL cc	7.0
	YP	8	Filter Cake/32	2	Mf	2.0	Water %	90.0	HTHP WL cc	
	O/W Ratio		ES		WPS					
Comments:	BUSAN=1, DYNA FIBER=21, ENGINEER=1, EVOTROL=7, EXWATE=120, EVOLUBE=1, GSX=12, NEWCARB=21, NEWGEL=16, NEWPHALT=5, NEWPAC R=5, NEWPHPA=5, NEWZAN D=8, POTASSIUM HYDROXIDE=2, SAWDUST=50, WALNUT=7									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION	Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	1,950	GPM	440	SPR		Slow PSI	
	Pump 2 Liner	6.5	Stroke Len	9.0	SPM	0	PSI	0	GPM		SPR		Slow PSI	
	Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	
	BHA Makeup								Length	921.4			Hours on BHA	2
	Up Weight	160	Dn Weight	95	RT Weight	130			Torque	12,500			Hours on Motor	2

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	BIT	7.875	0.000	1.00		12450966	SECURITY MM55M
2	MUD MOTOR	6.500	0.000	32.00		650113	1.5 DEG FBH 7/8 5.7 .24
3	MONEL	6.500	3.250	30.61		EN122-2	4.5 XO B X P
4	GAP SUB	6.500	3.250	5.49		650-001	4.5 XO BXP
5	MONEL	6.500	2.813	30.28		EN0815-12	
6	MONEL	6.500	2.813	30.22		EN0814-12	
7	DC	6.500	2.250	31.06		RIG	
8	(18) HWDP	4.500	2.313	547.01		RIG	
9	DRILLING JAR	6.500	2.813	31.68		67029E	
10	(6) HWDP	4.500	2.313	182.09		RIG	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	1,253	2,251	10,000
8100..320: Mud & Chemicals	9,394	29,797	55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	19,425	105,853	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel		11,027	20,000	8100..410: Mob/Demob		2,000	
8100..420: Bits & Reamers			17,500	8100..500: Roustabout Services	375	375	4,000
8100..510: Testing/Inspection/		1,610	1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental	2,650	8,270	17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	650	1,950	10,000	8100..535: Directional Drillin		31,500	65,000
8100..540: Fishing				8100..600: Surface Casing/Inte	1,246	20,810	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole	12,261	12,261	14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	2,500	10,000	35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	5,473	20,981		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work			25,000	8210..600: Production Casing		83,558	50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	55,227	385,762	675,000

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 06/20/2014

WELL NAME	THREE RIVERS 16-36T-820			AFE#	140618		SPUD DATE	06/16/2014		
WELL SITE CONSULTANT	JEREMY MEJORADO			PHONE#	435-219-4933		CONTRACTOR	Ensign 122		
TD AT REPORT	6,499'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS		62.0	DRLG DAYS SINCE SPUD	3	
ANTICIPATED TD	6,511'	PRESENT OPS	Rig down at 6,499'			GEOLOGIC SECT.				
DAILY MUD LOSS	SURF:	DH:	CUM. MUD LOSS			SURF:	30	DH:	507	
MUD COMPANY:			MUD ENGINEER:							
LAST BOP TEST	06/19/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		6,487	SSE	0	SSED	0

TIME BREAKDOWN	
NIPPLE DOWN B.O.P.	2.00

DETAILS			
Start	End	Hrs	
06:00	08:00	02:00	NIPPLE DOWN BOP - RIG RELEASED @ 0800 6/19/2014
05:55	05:55	00:00	SAFETY MEETING DAYS:NIPPLE DOWN BOP
			SAFETY MEETING NIGHTS:
			REGULATORY NOTICES: NONE.
			REGULATORY VISITS:NONE.
			INCIDENTS:NONE.
			SAFETY DRILLS:NONE

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	0.0	0.0	2,870.0	0.0	4,380.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

CEMENT JOB SUMMARY
SAFETY MEETING WITH HALLIBURTON - RIG UP CEMENTERS - TEST LINES TO 5000 PSI - PUMP 10 BBLS WATER SPACER, 20 BBLS 10.0 PPG SUPER FLUSH, 10 BBLS WATER SPACER, 146 BBLS 235 SACKS 11 PPG 3.5 YIELD LEAD CEMENT MIXED @ 20.92 GAL/SK, 96 BBLS 400 SKS 14 PPG 1.35 YIELD TAIL CEMENT MIXED @ 5.82 GAL/SK, SHUT DOWN WASH LINES DROP PLUG AND DISPLACE WITH 150.5 BBLS FRESH WATER - FINAL CIRCULATING PRESSURE 1350PSI BUMP PLUG AND HOLD 2000 PSI FOR TWO MINUTES - RELEASE PRESSURE FLOATS HELD - 3/4 TO FULL RETURNS DURING JOB 0 BBLS CEMENT TO SURFACE

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	06/19/2014	5 1/2	J-55	17	6,487		
Surface	06/01/2014	8 5/8	J-55	24	1,040		
Conductor	05/28/2014	16	ARJ-55	45	101		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
1	7.875	SECURITY	MM55M	12450966	12/12/12/12/12	0.552	1,060	6,499	1-1-WT-S-X-X--TD

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		55/106	440	1,850	3.05	2.00	143	71.50	52.50	5,439	103.60

RECENT MUD MOTORS:										
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
1	6.500	ENSIGN	FBH	650-056	7/8	1,060	6,499	06/15/2014	06/18/2014	

MUD MOTOR OPERATIONS:								
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1	26	0.24	2.00	143	71.50	52.50	5,439	103.60

SURVEYS									
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
06/19/2014	6,499	1.1	182.70	6,435	849.3	609.20	-592.77	0.0	MWD Survey Tool
06/19/2014	6,499	1.1	182.70	6,435	849.3	609.20	-592.77		MWD Survey Tool
06/19/2014	6,442	1.1	182.70	6,378	850.1	610.29	-592.72	0.1	MWD Survey Tool

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	1,950	GPM	440	SPR	_____	Slow PSI	_____
Pump 2 Liner	6.5	Stroke Len	9.0	SPM	0	PSI	0	GPM	_____	SPR	_____	Slow PSI	_____
Pump 32 Liner	_____	Stroke Len	_____	SPM	_____	PSI	_____	GPM	_____	SPR	_____	Slow PSI	_____
BHA Makeup	_____	_____	_____	_____	_____	_____	_____	Length	921.4	_____	_____	Hours on BHA	2
Up Weight	160	Dn Weight	95	RT Weight	130	_____	_____	Torque	12,500	_____	_____	Hours on Motor	2

BHA MAKEUP:							
#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	BIT	7.875	0.000	1.00		12450966	SECURITY MM55M
2	MUD MOTOR	6.500	0.000	32.00		650113	1.5 DEG FBH 7/8 5.7 .24
3	MONEL	6.500	3.250	30.61		EN122-2	4.5 XO B X P
4	GAP SUB	6.500	3.250	5.49		650-001	4.5 XO BXP
5	MONEL	6.500	2.813	30.28		EN0815-12	
6	MONEL	6.500	2.813	30.22		EN0814-12	
7	DC	6.500	2.250	31.06		RIG	
8	(18) HWDP	4.500	2.313	547.01		RIG	
9	DRILLING JAR	6.500	2.813	31.68		67029E	
10	(6) HWDP	4.500	2.313	182.09		RIG	

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees			4,500	8100..105: Insurance			2,500
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		23,310	30,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		2,251	10,000
8100..320: Mud & Chemicals	1,180	30,977	55,000	8100..325: Oil Base Mud Diesel			35,000
8100..400: Drilling Rig	1,575	107,428	135,000	8100..402: Drilling Rig Cleani			5,000
8100..405: Rig Fuel		11,027	20,000	8100..410: Mob/Demob		2,000	
8100..420: Bits & Reamers	13,598	13,598	17,500	8100..500: Roustabout Services		375	4,000
8100..510: Testing/Inspection/		1,610	1,000	8100..520: Trucking & Hauling		700	23,000
8100..530: Equipment Rental		8,270	17,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi		1,950	10,000	8100..535: Directional Drillin		31,500	65,000
8100..540: Fishing				8100..600: Surface Casing/Inte		20,810	35,000
8100..605: Cementing Work		19,510	25,000	8100..610: P & A			
8100..700: Logging - Openhole		12,261	14,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult		10,000	35,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	5,388	26,369		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			11,500	8200..530: Equipment Rental			20,000
8200..605: Cementing Work	33,809	33,809	25,000	8210..600: Production Casing		83,558	50,000
8210..620: Wellhead/Casing Hea			15,000	Total Cost	55,550	441,312	675,000

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 16-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0699 FSL 1311 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047542890000
PHONE NUMBER: 303 645-9810 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/17/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. First Production occurred on the TR16-36T-820 on 07/17/2014.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 04, 2014		
NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A	DATE 7/29/2014	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ OTHER _____
b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER _____

2. NAME OF OPERATOR:
Ultra Resources, Inc.

3. ADDRESS OF OPERATOR:

304 Inverness Way So. CITY Englewood STATE CO ZIP 80112

PHONE NUMBER:
(303) 645-9804

4. LOCATION OF WELL (FOOTAGES)

AT SURFACE: 699 FSL 1311 FEL 40.117222 109.668322

AT TOP PRODUCING INTERVAL REPORTED BELOW: 1345 FSL 1879 FEL 40.118975 109.670392

AT TOTAL DEPTH: 1316 FSL 1893 FEL 40.118894 109.670442

14. DATE SPUDDED:
5/28/2014

15. DATE T.D. REACHED:
6/18/2014

16. DATE COMPLETED:
7/23/2014

ABANDONED ☐ READY TO PRODUCE ☒

18. TOTAL DEPTH: MD 6,499
TVD 6,344

19. PLUG BACK T.D.: MD 6,486
TVD 6,331

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

Triple Combo, CBL

23.

WAS WELL CORED?

NO ☒ YES ☐

(Submit analysis)

WAS DST RUN?

NO ☒ YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☐ YES ☒

(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
24	16 arj55	45	0	101					
12 1/4	8 5/8 j-55	24	0	1,040				0	
7 7/8	5 1/2 j-55	17	0	6,487		700		0	
						635		0	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8	4,600							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A) Lower GR	4,596	6,377		
(B)				
(C)				
(D)				

27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
4,596 6,377		273	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

WAS WELL HYDRAULICALLY FRACTURED? YES ☒ NO ☐

IF YES - DATE FRACTURED: 7/11/2014

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4596 to 6377	Fracture/ Stimulate 7 Stages

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS

☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION

☐ GEOLOGIC REPORT

☐ CORE ANALYSIS

☐ DST REPORT

☒ OTHER: _____

☒ DIRECTIONAL SURVEY

30. WELL STATUS:

POW

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 7/17/2014	TEST DATE: 7/29/2014	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL - BBL: 113	GAS - MCF: 79	WATER - BBL: 579	PROD. METHOD: Gas Pumping
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Used on lease

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Upper Green River	2,412
				Mahogany	3,819
				Lower Green River	4,571
				Wasatch	6,379

35. ADDITIONAL REMARKS (Include plugging procedure)

Frac material used: 7000 gal HCl Acid, 1072003 gal FR-66 Water, 266204 gal DeltaFrac Fluid, 1139278 lbs White Sand

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Jenna Anderson

TITLE Permitting Specialist

SIGNATURE 

DATE 8/21/2014

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

☐ Proposed
☒ As Is

THREE RIVERS 16-36T-820 GL: Missing, KB: 4,697.0
 Sec 16, 8S, 20E Uintah County, Utah

	Size	Weight	Grade	Depth	Sks/Cmt
Conductor	16	45	ARJ-55	101	
Surface	8 5/8	24	J-55	1040	700
Production	5 1/2	17	J-55	6487	635
Tubing				4591	
Tubing	2.875			4538	
Tubing	2.875	6.5	J-55	4507	
Tubing	2.875			16	
Cement Top				0	


STAGE	ZONE 1	ZONE 2	ZONE 3	ZONE 4	ZONE 5	ZONE 6	ZONE 7
1	6376-6377	6369-6371	6361-6362	6349-6350	6315-6316	6310-6311	6298-6299
2	6219-6221	6209-6210	6201-6202	6193-6194	6185-6186	6174-6175	6164-6165
3	6058-6060	6045-6046	6020-6021	6009-6010	5984-5985	5952-5953	5934-5935
4	5805-5807	5793-5794	5759-5760	5747-5748	5735-5736	5721-5722	5709-5710
5	5559-5561	5529-5530	5512-5513	5449-5450	5433-5434	5419-5420	5405-5406
6	5106-5108	5053-5054	5048-5049	5040-5041	4994-4995	4934-4935	4921-4922
7	4762-4764	4741-4742	4734-4735	4725-4726	4716-4717	4683-4684	4677-4678


Stage	Date	Av.Rate	Av.Press	Proppant	CleanFluid	Tracer	Screenout
1	07/11/2014	60.7	2,981	127,100	4,021		N
2	07/11/2014	61.0	2,512	155,000	4,783		N
3	07/11/2014	56.4	2,145	189,852	5,840		N
4	07/12/2014	56.2	2,765	176,526	4,921		N
5	07/12/2014	60.8	2,346	195,200	5,271		N
6	07/12/2014	60.6	2,310	151,900	3,989		N
7	07/12/2014	60.9	1,824	143,700	3,916		N
Totals:				1,139,278	32,741		

Actual Formation or Depth	Top	Sand Type	Amount
		Gross Sand Drilled	
		Gross Sand Logged	
		Net Sand	
		Net Pay	

Move In	Spud Date	TD Date	Rig Release	1st Prod	Full Sales
06/01/2014	06/16/2014	06/18/2014	06/19/2014	07/17/2014	

Tbg Date	Depth	OD	ID	Weight	Grade	Thread	Csg Size	1st Jt	# Joints	Coil
07/23/2014	4,591.000						5.5		143	N
07/23/2014	4,538.000						5.5		143	N
07/23/2014	16.000						5.5		143	N





ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
 Field: UTAH COUNTY Well: Three Rivers 16-36T-820
 Facility: Sec 16-T8S-R20E Wellbore: Three Rivers 16-36T-820 PWB

Plot referenced south to Three Rivers 16-36T-820 PWB

True vertical depths are referenced to Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)

Grid System: NAD83 (Lambert Utah SP. Central Zone 43002) U.S. feet

Measured depths are referenced to Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)

North Reference: True north

Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mean Sea Level: +887 feet



Scale: True distance

Mean Sea Level to Mud line (SL) Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)

Depths are in feet

Coordinates and in feet referenced to SL

Created by: geologists on 10/20/14





Actual Wellpath Report

Three Rivers 16-36T-820 AWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 AWB
Facility	Sec.16-T8S-R20E		

REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	EWilliams
Scale	0.999911	Report Generated	8/5/2014 at 3:28:27 PM
Convergence at slot	1.17° East	Database/Source file	WellArchitectDB/Three_Rivers_16-36T-820_AWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-577.63	1974.80	2152625.02	7216667.36	40°07'02.000"N	109°40'05.960"W
Facility Reference Pt			2150639.03	7217204.54	40°07'07.709"N	109°40'31.379"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Facility Vertical Datum
Horizontal Reference Pt	Slot	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mean Sea Level
Vertical Reference Pt	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT) to Mud Line at Slot (Three Rivers 16-36T-820 (699' FSL & 1311' FEL))
MD Reference Pt	Rig on Three Rivers 16-36T-820 (699' FSL & 1311' FEL) (RT)	Section Origin
Field Vertical Reference	Mean Sea Level	Section Azimuth



Actual Wellpath Report

Three Rivers 16-36T-820 AWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 AWP
Facility	Sec.16-T8S-R20E		

WELLPATH DATA (70 stations) † = interpolated/extrapolated station

MD (ft)	Inclination (°)	Azimuth (°)	TVD (ft)	Vert Sect (ft)	North (ft)	East (ft)	Latitude	Longitude	DLS (ft/100ft)	Comments
0.00†	0.000	201.300	0.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
13.00	0.000	201.300	13.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
101.00	0.000	0.000	101.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
1040.00	0.000	0.000	1040.00	0.00	0.00	0.00	40°07'02.000"N	109°40'05.960"W	0.00	
1097.00	1.800	201.300	1096.99	-0.40	-0.83	-0.33	40°07'01.992"N	109°40'05.964"W	3.16	
1188.00	2.300	172.900	1187.93	-2.55	-3.98	-0.62	40°07'01.961"N	109°40'05.968"W	1.23	
1279.00	1.100	148.700	1278.89	-4.91	-6.54	0.06	40°07'01.935"N	109°40'05.959"W	1.51	
1369.00	0.700	336.500	1368.89	-5.23	-6.77	0.29	40°07'01.933"N	109°40'05.956"W	2.00	
1460.00	3.000	335.200	1459.84	-2.43	-4.10	-0.93	40°07'01.959"N	109°40'05.972"W	2.53	
1550.00	4.400	326.900	1549.65	3.23	0.93	-3.80	40°07'02.009"N	109°40'06.009"W	1.66	
1641.00	6.200	317.100	1640.26	11.60	7.46	-9.06	40°07'02.074"N	109°40'06.077"W	2.21	
1731.00	8.200	319.500	1729.54	22.87	15.90	-16.53	40°07'02.157"N	109°40'06.173"W	2.25	
1822.00	10.000	321.300	1819.39	37.25	27.00	-25.69	40°07'02.267"N	109°40'06.291"W	2.00	
1913.00	11.700	321.100	1908.76	54.36	40.35	-36.42	40°07'02.399"N	109°40'06.429"W	1.87	
2003.00	14.300	317.800	1996.45	74.59	55.69	-49.62	40°07'02.550"N	109°40'06.599"W	3.00	
2094.00	16.700	317.200	2084.13	98.90	73.61	-66.06	40°07'02.727"N	109°40'06.810"W	2.64	
2184.00	18.700	319.200	2169.87	126.26	94.02	-84.27	40°07'02.929"N	109°40'07.045"W	2.32	
2275.00	21.800	320.600	2255.24	157.73	118.13	-104.54	40°07'03.167"N	109°40'07.306"W	3.45	
2366.00	22.800	318.100	2339.43	192.25	144.31	-127.04	40°07'03.426"N	109°40'07.595"W	1.51	
2412.00†	23.306	316.745	2381.76	210.26	157.57	-139.22	40°07'03.557"N	109°40'07.752"W	1.59	Top Green River
2456.00	23.800	315.500	2422.09	227.83	170.24	-151.41	40°07'03.682"N	109°40'07.909"W	1.59	
2547.00	23.700	315.500	2505.38	264.44	196.38	-177.10	40°07'03.941"N	109°40'08.240"W	0.11	
2637.00	24.500	315.600	2587.54	301.16	222.62	-202.83	40°07'04.200"N	109°40'08.571"W	0.89	
2728.00	25.400	316.600	2670.05	339.52	250.28	-229.45	40°07'04.473"N	109°40'08.913"W	1.09	
2819.00	25.800	316.600	2752.11	378.82	278.85	-256.46	40°07'04.756"N	109°40'09.261"W	0.44	
2909.00	26.100	315.900	2833.04	418.18	307.29	-283.70	40°07'05.037"N	109°40'09.612"W	0.48	
3000.00	26.200	316.300	2914.72	458.26	336.19	-311.51	40°07'05.322"N	109°40'09.970"W	0.22	
3090.00	26.200	317.400	2995.48	497.99	365.18	-338.68	40°07'05.609"N	109°40'10.319"W	0.54	
3181.00	25.100	316.800	3077.51	537.37	394.04	-365.49	40°07'05.894"N	109°40'10.665"W	1.24	
3271.00	25.100	319.200	3159.01	575.54	422.40	-391.03	40°07'06.174"N	109°40'10.993"W	1.13	
3362.00	23.200	321.000	3242.05	612.75	450.95	-414.93	40°07'06.456"N	109°40'11.301"W	2.24	
3453.00	20.300	318.500	3326.56	646.44	476.71	-436.67	40°07'06.711"N	109°40'11.581"W	3.34	
3543.00	19.400	314.900	3411.22	676.98	498.95	-457.61	40°07'06.931"N	109°40'11.850"W	1.69	
3634.00	18.200	315.200	3497.36	706.26	519.70	-478.33	40°07'07.136"N	109°40'12.117"W	1.32	
3724.00	16.700	316.400	3583.21	733.23	539.04	-497.15	40°07'07.327"N	109°40'12.359"W	1.71	
3815.00	16.700	319.300	3670.38	759.37	558.42	-514.69	40°07'07.518"N	109°40'12.585"W	0.92	
3819.00†	16.607	319.331	3674.21	760.51	559.29	-515.44	40°07'07.527"N	109°40'12.595"W	2.35	Mahogany
3905.00	14.600	320.100	3757.04	783.64	576.93	-530.40	40°07'07.701"N	109°40'12.787"W	2.35	
3996.00	12.400	320.500	3845.52	804.86	593.27	-543.97	40°07'07.863"N	109°40'12.962"W	2.42	
4087.00	10.400	322.300	3934.72	822.82	607.31	-555.21	40°07'08.001"N	109°40'13.107"W	2.23	
4177.00	8.000	319.200	4023.55	837.18	618.48	-564.27	40°07'08.112"N	109°40'13.223"W	2.72	
4268.00	5.800	323.500	4113.89	848.09	626.97	-571.15	40°07'08.196"N	109°40'13.312"W	2.48	
4358.00	3.800	324.700	4203.57	855.58	633.06	-575.58	40°07'08.256"N	109°40'13.369"W	2.22	
4449.00	1.300	342.000	4294.47	859.52	636.51	-577.64	40°07'08.290"N	109°40'13.395"W	2.84	
4540.00	0.800	321.100	4385.46	861.10	637.98	-578.36	40°07'08.305"N	109°40'13.405"W	0.68	



Actual Wellpath Report

Three Rivers 16-36T-820 AWP

Page 3 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 AWB
Facility	Sec.16-T8S-R20E		

WELLPATH DATA (70 stations) † = interpolated/extrapolated station

MD (ft)	Inclination (°)	Azimuth (°)	TVD (ft)	Vert Sect (ft)	North (ft)	East (ft)	Latitude	Longitude	DL5 (%/100ft)	Comments
4571.00†	0.825	314.652	4416.45	861.54	638.31	-578.63	40°07'08.308"N	109°40'13.408"W	0.31	Lower Green River
4596.00†	0.853	309.781	4441.45	861.91	638.55	-578.92	40°07'08.310"N	109°40'13.412"W	0.31	Top of Production
4630.00	0.900	303.700	4475.45	862.41	638.86	-579.34	40°07'08.313"N	109°40'13.417"W	0.31	
4721.00	0.800	301.900	4566.44	863.72	639.60	-580.47	40°07'08.320"N	109°40'13.432"W	0.11	
4811.00	0.800	280.800	4656.43	864.82	640.03	-581.62	40°07'08.325"N	109°40'13.447"W	0.33	
4902.00	1.000	278.900	4747.42	865.94	640.29	-583.03	40°07'08.327"N	109°40'13.465"W	0.22	
4993.00	1.000	250.640	4838.41	866.86	640.15	-584.57	40°07'08.326"N	109°40'13.485"W	0.54	
5083.00	1.100	224.800	4928.39	867.11	639.27	-585.92	40°07'08.317"N	109°40'13.502"W	0.53	
5174.00	0.800	218.800	5019.38	866.96	638.16	-586.93	40°07'08.306"N	109°40'13.515"W	0.35	
5264.00	1.100	206.900	5109.37	866.54	636.90	-587.71	40°07'08.294"N	109°40'13.525"W	0.40	
5355.00	1.400	197.300	5200.34	865.66	635.06	-588.44	40°07'08.276"N	109°40'13.534"W	0.40	
5445.00	1.500	189.600	5290.32	864.36	632.85	-588.96	40°07'08.254"N	109°40'13.541"W	0.24	
5536.00	1.600	190.600	5381.28	862.85	630.42	-589.40	40°07'08.230"N	109°40'13.547"W	0.11	
5627.00	1.500	188.000	5472.25	861.31	628.00	-589.80	40°07'08.206"N	109°40'13.552"W	0.13	
5717.00	1.500	191.100	5562.22	859.84	625.67	-590.19	40°07'08.183"N	109°40'13.557"W	0.09	
5808.00	1.500	187.800	5653.19	858.35	623.32	-590.58	40°07'08.160"N	109°40'13.562"W	0.09	
5898.00	1.400	189.300	5743.16	856.90	621.07	-590.91	40°07'08.137"N	109°40'13.566"W	0.12	
5989.00	1.300	198.200	5834.13	855.69	618.99	-591.42	40°07'08.117"N	109°40'13.573"W	0.25	
6079.00	1.400	195.800	5924.11	854.59	616.97	-592.03	40°07'08.097"N	109°40'13.581"W	0.13	
6170.00	1.100	183.000	6015.09	853.38	615.03	-592.38	40°07'08.078"N	109°40'13.585"W	0.45	
6260.00	1.000	188.200	6105.07	852.26	613.39	-592.54	40°07'08.061"N	109°40'13.587"W	0.15	
6351.00	1.000	186.500	6196.06	851.23	611.81	-592.74	40°07'08.046"N	109°40'13.590"W	0.03	
6379.00†	1.030	185.252	6224.05	850.89	611.32	-592.79	40°07'08.041"N	109°40'13.590"W	0.13	Wasatch
6442.00	1.100	182.700	6287.04	850.08	610.15	-592.87	40°07'08.029"N	109°40'13.591"W	0.13	End of Surveys
6499.00	1.100	182.700	6344.03	849.30	609.06	-592.93	40°07'08.019"N	109°40'13.592"W	0.00	Projection to Bit (BHL)



Actual Wellpath Report

Three Rivers 16-36T-820 AWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 AWB
Facility	Sec.16-T8S-R20E		

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
Three Rivers 16-36T-820 Target on Plat Radius: 50' 1300' FSL & 1880' FEL		4416.00	593.00	-580.33	2152032.72	7217248.29	40°07'07.860"N	109°40'13.430"W	circle
Three Rivers 16-36T-820 Driller's Target Radius: 5' 1349' FSL & 1875' FEL		4416.00	641.00	-575.00	2152037.07	7217296.39	40°07'08.334"N	109°40'13.361"W	circle

WELLPATH COMPOSITION - Ref Wellbore: Three Rivers 16-36T-820 AWB Ref Wellpath: Three Rivers 16-36T-820 AWP

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
13.00	101.00	Unknown Tool (Standard)	Conductor	Three Rivers 16-36T-820 AWB
101.00	1040.00	Unknown Tool (Standard)	Surface	Three Rivers 16-36T-820 AWB
1040.00	6442.00	Unknown Tool (Standard)	MWD	Three Rivers 16-36T-820 AWB
6442.00	6499.00	Blind Drilling (std)	Projection to bit	Three Rivers 16-36T-820 AWB



Actual Wellpath Report

Three Rivers 16-36T-820 AWP

Page 5 of 5



REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers 16-36T-820 (699' FSL & 1311' FEL)
Area	Three Rivers	Well	Three Rivers 16-36T-820
Field	UINTAH COUNTY	Wellbore	Three Rivers 16-36T-820 AWB
Facility	Sec.16-T8S-R20E		

WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
2412.00	23.306	316.745	2381.76	Top Green River
3819.00	16.607	319.331	3674.21	Mahogany
4571.00	0.825	314.652	4416.45	Lower Green River
4596.00	0.853	309.781	4441.45	Top of Production
6379.00	1.030	185.252	6224.05	Wasatch
6442.00	1.100	182.700	6287.04	End of Surveys
6499.00	1.100	182.700	6344.03	Projection to Bit (BHL)

ULTRA RESOURCES, INC.
DAILY COMPLETION REPORT FOR 07/03/2014 TO 07/17/2014

Well Name	THREE RIVERS 16-36T-820	Frac Planned	7
Location:	UINTAH County, UTAH(SESE 16 8S 20E)	AFE#	140618
Total Depth Date:	06/18/2014 TD 6,499	Formation:	(Missing)
Production Casing:	Size 5 1/2 Wt 17 Grade J-55 Set At 6,487	GL:	KB: 4,697

Date: 07/03/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:	Duncan		
Work Objective:	Logging		
Contractors:	J-W		
Completion Rig:	J-W	Supervisor Phone: 435-828-1472	
Upcoming Activity:	Completion		
Activities			
1200-1500	MIRU JW WLU, run 4.65" gauge ring fr/surface to 6450'. POH w/gauge ring. Run CBL/GR/CCL fr/6435' to surface. TOC @ 1250'. RDMO WLU.		
Costs (\$):	Daily: 9,650	Cum: 9,650	AFE: 948,500

Date: 07/07/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:	Duncan		
Work Objective:	Prep for frac work		
Contractors:	Knight, BC, R&R		
Completion Rig:	(Missing)	Supervisor Phone: 435-828-1472	
Upcoming Activity:	Completion		
Activities			
0700-1700	Set flow back tanks, and iron. MINU Knight 5K BOP.		
Costs (\$):	Daily: 0	Cum: 9,650	AFE: 948,500

Date: 07/08/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:	Duncan		
Work Objective:	Prep for frac work		
Contractors:	RBS, R&R, RNI		
Completion Rig:	(Missing)	Supervisor Phone: 435-828-1472	
Upcoming Activity:	Completion		
Activities			
1110-1200	MIRU RBS Test Unit, and test csg, WH, Flow back lines, and BOP to 4,250 psig, good test. RDMO Testers		
Costs (\$):	Daily: 11,107	Cum: 20,757	AFE: 948,500

Date: 07/09/2014			
Tubing:		OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD: 6,486
Supervisor:		Duncan	
Work Objective:		Perforating	
Contractors:		J-W	
Completion Rig:		J-W	Supervisor Phone: 435-828-1472
Upcoming Activity:		Completion	
Activities			
0800-0900		Perforate stage 1.	
Costs (\$):	Daily: 0	Cum: 20,757	AFE: 948,500

Date: 07/10/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:	Fletcher		
Work Objective:	Prep for frac work		
Contractors:	(Missing)		
Completion Rig:	(Missing)	Supervisor Phone: 3036459812	
Upcoming Activity:	Completion		
Costs (\$):	Daily: 0	Cum: 20,757	AFE: 948,500

Date: 07/11/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD:	6,486
Supervisor:	Hutchinson, Scott		
Work Objective:	Perf, Frac, and Flowback		
Contractors:	R&R, JW-WL, HAL-FRAC		
Completion Rig:	HAL - Blue UT, J-W	Supervisor Phone: 307.354.6007/307.350.8487	
Upcoming Activity:	Perf, Frac, and Flowback		
Activities			
0800-0830	Rig up Frac to wellhead.		
0830-0945	Frac stage 1.		
0945-1245	Perforate stage 2 (6080-6221). Set 5.5" FTFP @ 6239'. Contractor Miscue.		
1245-1425	Wait to frac TR 16-46T-820.		
1425-1600	Frac stage 2.		
1600-1700	Perforate stage 3 (5868-6060). Set 5.5 FTFP @ 6078'.		
1700-1755	Wait to frac TR 16-46T-820.		
1755-2120	Work on blender & pumps.		
2120-2315	Frac stage 3.		
2315-0015	Perforate stage 4 (5603-5807) Set 5.5" FTFP at 5827'.		
Costs (\$):	Daily: 1,481	Cum: 22,238	AFE: 948,500

Date: 07/12/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD:	6,486
Supervisor:	Hutchinson, Scott		
Work Objective:	Perf, Frac, and Flowback		
Contractors:	R&R, JW-WL, HAL-FRAC, IPS, QES, RNI		
Completion Rig:	HAL - Blue UT, IPS CT 2", J-W	Supervisor Phone:	307.354.6007/307.350.8487
Upcoming Activity:	Drill out plug		
Activities			
2315-0015	Perforate stage 4 (5603-5807) Set 5.5" FTFP at 5827'.		
0015-0125	Wait to frac TR16-46T-820.		
0125-0315	Frac stage 4.		
0315-0415	Perforate stage 5 (5332-5561) Set 5.5" FTFP at 5581'.		
0415-0535	Wait to frac TR16-46T-820.		
0535-0715	Frac stage 5.		
0715-0810	Perforate stage 6 (4800-5108). Set 5.5" FTFP @ 5128'.		
0810-0910	Wait to frac TR16-46T-820.		
0910-1030	Frac stage 6.		
1030-1125	Perforate stage 7 (4596-4764). Set 5.5" FTFP @ 4784'.		
1125-1205	Wait to frac TR16-46T-820.		
1205-1205	Frac stage 7.		
1330-1331	SICP = 1350. Rig down.		
2100-2345	MIRU IPS CTU NU. lub. Fill coil with water. Install coil connect. Pull test to 25,000# & pressure test to 3000		
	psi. Break lubricator off 7-1/16" BOP. New QES BHA as follows: Coil Connector, Bi-Directional jar, MHA Dual		
	Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect, motor and 5 blade 4.625" mill.		
	Reconnect lubricator. Function test motor,		
	Pressure test to 3000 psi.		
2345-0000	Safety Meeting-Review location hazards including, WHP, crane operations, the use land guides while backin		
	Review incident reporting of property damage, & personnel injuries. Slips trips and falls, Establish smoking		
	area & Muster area.		
0000-0100	Open Rams Well Pressure 1000 PSI. RIH with mill and motor to plug @ 4784'. (Coil depth 4790'). Drill plug.		
	900 PSI.		
Costs (\$):	Daily: 435,317	Cum: 457,554	AFE: 948,500

Date: 07/13/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD:	6,486
Supervisor:	Stringham/Scott		
Work Objective:	Drill out plug	SSE:	1
Contractors:	IPS,R&R,ETS,RNI		
Completion Rig:	IPS CT 2"	Supervisor Phone: 4357902326/3073508487	
Upcoming Activity:	Flow test well		
Activities			
0000-0100	Open Rams Well Pressure 1000 PSI. RIH with mill and motor to plug @ 4784'. (Coil depth 4790'). Drill plug. 900 PSI.		
0100-0135	Pump a 10 bbl gel sweep. RIH to plug @ 5128'. Tag sand at 4978', wash sand to plug. (Coil depth 5137'). Dr plug. 900 PSI.		
0135-0215	Pump a 10 bbl gel sweep. RIH to plug @ 5581'. Tag sand at 5461', wash sand to plug. (Coil depth 5591'). Dr plug. 950 PSI.		
0215-0255	Pump a 20 bbl gel sweep. RIH to plug @ 5827'. Tag sand at 5738', wash sand to plug. (Coil depth 5838').Short Trip. Drill plug. 900 PSI.		
0255-0325	Pump a 10 bbl gel sweep. RIH to plug @ 6078'. Tag sand at 6000', wash sand to plug. (Coil depth 6085'). Dr plug. 900 PSI.		
0325-0405	Pump a 10 bbl gel sweep. RIH to plug @ 6239'. Tag sand at 6179', wash sand to plug. (Coil depth 6247'). Dr plug. 900 PSI.		
0405-0545	RIH to PBTD @ 6486'. Pump 20 bbl gel sweep, 10 bbl water spacer & 20 bbl gel sweep. Coil PBTD @ 6470'. Make 500' short trip and retag PBTD. POOH @ 50 ft/min for 30 min and then continue POOH. Close Bottom ram, SICP 1050#.		
0545-0630	SICP 570#. ND lubricator, swing over to the TR 16-46T-820.		
0630-0631	Turn well over to flow back. Open well on a 14/64" choke @ 950 PSI.		
Costs (\$):	Daily: 39,215	Cum: 496,770	AFE: 948,500

Date: 07/14/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD:	6,486
Supervisor:	Stringham/Duncan		
Work Objective:	Flow test well		
Contractors:	R&R, RNI		
Completion Rig:	(Missing)	Supervisor Phone:	4357902326/4358281472
Upcoming Activity:	Turned over to Production Dept		
Costs (\$):	Daily: 343	Cum: 497,113	AFE: 948,500

Date: 07/15/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"	PBTD:	6,486
Supervisor:	Duncan		
Work Objective:	Flow test well		
Contractors:	(Missing)		
Completion Rig:	(Missing)	Supervisor Phone:	4358281472
Upcoming Activity:	Flow test well		
Costs (\$):	Daily: 6,448	Cum: 503,561	AFE: 948,500

Date: 07/16/2014			
Tubing:	OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:	Stringham/Duncan		
Work Objective:	Flow test well		
Contractors:	R&R,RNI		
Completion Rig:	(Missing)		Supervisor Phone: 4357902326/4358281472
Upcoming Activity:	Turned over to Production Dept		
Costs (\$):	Daily: 25,904	Cum: 529,464	AFE: 948,500

Date: 07/17/2014				
Tubing:		OD: 2.875" ID: Joints: 143" Depth Set: 4,600"		PBTD: 6,486
Supervisor:		Fletcher		
Work Objective:		Turned over to Production Dept		
Contractors:		(Missing)		
Completion Rig:		(Missing)		Supervisor Phone: 3036459812
Upcoming Activity:				
Costs (\$):	Daily:	19,338	Cum:	548,802
			AFE:	948,500

ULTRA RESOURCES, INC.
PERFORATION AND FRAC SUMMARY FOR THREE RIVERS 16-36T-820

Well Name: THREE RIVERS 16-36T-820			Fracs Planned: 7		
Location: UINTAH County, UTAH (SESE 016 8S 20E)					
Stage 1		Frac Date: 07/11/2014	Avg Rate: 60.7 BPM	Avg Pressure: 2,981 PSI	
Initial Completion		Proppant: 127,100 lbs total	Max Rate: 63.2 BPM	Max Pressure: 4,143 PSI	
127100 lbs Ottawa					
Initial Annulus Pressure: 75		Final Annulus Pressure: 79	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,845 PSI	Base BBLs to Recover: 4,021 BBLs		
Pseudo Frac Gradient: 0.722 PSI/FT		Pseudo Frac Gradient: 13.887 LB/GAL			
		Net Pressure: -248 psi	Total BBLs to Recover: 4,021 BBLs		
Breakdown Pressure: 3277		Breakdown Rate: 9.5	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
12	07/09/2014	3		6,241	6,242
11	07/09/2014	3		6,251	6,252
10	07/09/2014	3		6,269	6,270
9	07/09/2014	3		6,275	6,276
8	07/09/2014	3		6,285	6,286
7	07/09/2014	3		6,298	6,299
6	07/09/2014	3		6,310	6,311
5	07/09/2014	3		6,315	6,316
4	07/09/2014	3		6,349	6,350
3	07/09/2014	3		6,361	6,362
2	07/09/2014	3		6,369	6,371
1	07/09/2014	3		6,376	6,377
Stage 2		Frac Date: 07/11/2014	Avg Rate: 61.0 BPM	Avg Pressure: 2,512 PSI	
Initial Completion		Proppant: 155,000 lbs total	Max Rate: 61.7 BPM	Max Pressure: 3,547 PSI	
155000 lbs Ottawa					
Initial Annulus Pressure: 0		Final Annulus Pressure: 0	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,554 PSI	Base BBLs to Recover: 4,783 BBLs		
Pseudo Frac Gradient: 0.683 PSI/FT		Pseudo Frac Gradient: 13.127 LB/GAL			
		Net Pressure: 997 psi	Total BBLs to Recover: 4,783 BBLs		
Breakdown Pressure: 2950		Breakdown Rate: 9.6	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
12	07/11/2014	3		6,080	6,081
11	07/11/2014	3		6,097	6,098
10	07/11/2014	3		6,119	6,120
9	07/11/2014	3		6,133	6,134
8	07/11/2014	3		6,144	6,145
7	07/11/2014	3		6,164	6,165
6	07/11/2014	3		6,174	6,175
5	07/11/2014	3		6,185	6,186
4	07/11/2014	3		6,193	6,194
3	07/11/2014	3		6,201	6,202
2	07/11/2014	3		6,209	6,210
1	07/11/2014	3		6,219	6,221
Stage 3		Frac Date: 07/11/2014	Avg Rate: 56.4 BPM	Avg Pressure: 2,145 PSI	
Initial Completion		Proppant: 189,852 lbs total	Max Rate: 62.1 BPM	Max Pressure: 2,671 PSI	
189852 lbs Ottawa					
Initial Annulus Pressure: 0		Final Annulus Pressure: 18	Pump Down Volume:		
PreFrac SICP:		ISIP: 1,761 PSI	Base BBLs to Recover: 5,840 BBLs		
Pseudo Frac Gradient: 0.724 PSI/FT		Pseudo Frac Gradient: 13.911 LB/GAL			
		Net Pressure: 222 psi	Total BBLs to Recover: 5,840 BBLs		
Breakdown Pressure: 1413		Breakdown Rate: 8.7	Perfs Open:		
ScreenOut: No		Tracer: (None)			
Zones:	Perf Date	SPF	Perf Interval:	From	To
12	07/11/2014	3		5,868	5,869
11	07/11/2014	3		5,880	5,881
10	07/11/2014	3		5,891	5,892
9	07/11/2014	3		5,903	5,904
8	07/11/2014	3		5,924	5,925
7	07/11/2014	3		5,934	5,935
6	07/11/2014	3		5,952	5,953
5	07/11/2014	3		5,984	5,985
4	07/11/2014	3		6,009	6,010
3	07/11/2014	3		6,020	6,021
2	07/11/2014	3		6,045	6,046
1	07/11/2014	3		6,058	6,060

Stage 4	Frac Date: 07/12/2014	Avg Rate: 56.2 BPM	Avg Pressure: 2,765 PSI
Initial Completion	Proppant: 176,526 lbs total 176526 lbs Ottawa	Max Rate: 60.4 BPM	Max Pressure: 3,499 PSI
	Initial Annulus Pressure: 25	Final Annulus Pressure: 29	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,880 PSI	Base BBLs to Recover: 4,921 BBLs
	Pseudo Frac Gradient: 0.757 PSI/FT	Pseudo Frac Gradient: 14.548 LB/GAL	
		Net Pressure: 1413 psi	Total BBLs to Recover: 4,921 BBLs
	Breakdown Pressure: 3023	Breakdown Rate: 9.2	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	07/11/2014	3	5,603 5,604
11	07/11/2014	3	5,621 5,622
10	07/11/2014	3	5,641 5,642
9	07/11/2014	3	5,679 5,680
8	07/11/2014	3	5,690 5,691
7	07/11/2014	3	5,709 5,710
6	07/11/2014	3	5,721 5,722
5	07/11/2014	3	5,735 5,736
4	07/11/2014	3	5,747 5,748
3	07/11/2014	3	5,759 5,760
2	07/11/2014	3	5,793 5,794
1	07/11/2014	3	5,805 5,807
Stage 5	Frac Date: 07/12/2014	Avg Rate: 60.8 BPM	Avg Pressure: 2,346 PSI
Initial Completion	Proppant: 195,200 lbs total 195200 lbs Ottawa	Max Rate: 62.5 BPM	Max Pressure: 3,180 PSI
	Initial Annulus Pressure: 30	Final Annulus Pressure: 34	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,855 PSI	Base BBLs to Recover: 5,271 BBLs
	Pseudo Frac Gradient: 0.767 PSI/FT	Pseudo Frac Gradient: 14.737 LB/GAL	
		Net Pressure: 255 psi	Total BBLs to Recover: 5,271 BBLs
	Breakdown Pressure: 2380	Breakdown Rate: 9.2	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	07/12/2014	3	5,332 5,333
11	07/12/2014	3	5,341 5,342
10	07/12/2014	3	5,366 5,367
9	07/12/2014	3	5,381 5,382
8	07/12/2014	3	5,390 5,391
7	07/12/2014	3	5,405 5,406
6	07/12/2014	3	5,419 5,420
5	07/12/2014	3	5,433 5,434
4	07/12/2014	3	5,449 5,450
3	07/12/2014	3	5,512 5,513
2	07/12/2014	3	5,529 5,530
1	07/12/2014	3	5,559 5,561
Stage 6	Frac Date: 07/12/2014	Avg Rate: 60.6 BPM	Avg Pressure: 2,310 PSI
Initial Completion	Proppant: 151,900 lbs total 151900 lbs Ottawa	Max Rate: 63.4 BPM	Max Pressure: 3,970 PSI
	Initial Annulus Pressure: 34	Final Annulus Pressure: 35	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,369 PSI	Base BBLs to Recover: 3,989 BBLs
	Pseudo Frac Gradient: 0.701 PSI/FT	Pseudo Frac Gradient: 13.477 LB/GAL	
		Net Pressure: -206 psi	Total BBLs to Recover: 3,989 BBLs
	Breakdown Pressure: 2694	Breakdown Rate: 9.2	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	07/12/2014	3	4,800 4,801
11	07/12/2014	3	4,822 4,823
10	07/12/2014	3	4,845 4,846
9	07/12/2014	3	4,879 4,880
8	07/12/2014	3	4,888 4,889
7	07/12/2014	3	4,921 4,922
6	07/12/2014	3	4,934 4,935
5	07/12/2014	3	4,994 4,995
4	07/12/2014	3	5,040 5,041
3	07/12/2014	3	5,048 5,049
2	07/12/2014	3	5,053 5,054
1	07/12/2014	3	5,106 5,108

Stage 7	Frac Date: 07/12/2014	Avg Rate: 60.9 BPM	Avg Pressure: 1,824 PSI
Initial Completion	Proppant: 143,700 lbs total	Max Rate: 61.2 BPM	Max Pressure: 2,295 PSI
	143700 lbs Ottawa		
	Initial Annulus Pressure: 29	Final Annulus Pressure: 27	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,358 PSI	Base BBLs to Recover: 3,916 BBLs
	Pseudo Frac Gradient: 0.718 PSI/FT	Pseudo Frac Gradient: 13.805 LB/GAL	
		Net Pressure: 192 psi	Total BBLs to Recover: 3,916 BBLs
	Breakdown Pressure: 1265	Breakdown Rate: 9.6	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
12	07/12/2014	3	4,596 4,597
11	07/12/2014	3	4,604 4,605
10	07/12/2014	3	4,611 4,612
9	07/12/2014	3	4,622 4,623
8	07/12/2014	3	4,631 4,632
7	07/12/2014	3	4,677 4,678
6	07/12/2014	3	4,683 4,684
5	07/12/2014	3	4,716 4,717
4	07/12/2014	3	4,725 4,726
3	07/12/2014	3	4,734 4,735
2	07/12/2014	3	4,741 4,742
1	07/12/2014	3	4,762 4,764

Hydraulic Fracturing Fluid Product Component Information Disclosure

Job Start Date:	7/11/2014
Job End Date:	7/12/2014
State:	Utah
County:	Uintah
API Number:	43-047-54289-00-00
Operator Name:	Ultra Resources
Well Name and Number:	Three Rivers 16-36T-820
Longitude:	-109.66828000
Latitude:	40.11721000
Datum:	NAD27
Federal/Tribal Well:	NO
True Vertical Depth:	7,500
Total Base Water Volume (gal):	1,371,187
Total Base Non Water Volume:	0



Hydraulic Fracturing Fluid Composition:

Trade Name	Supplier	Purpose	Ingredients	Chemical Abstract Service Number (CAS #)	Maximum Ingredient Concentration in Additive (% by mass)**	Maximum Ingredient Concentration in HF Fluid (% by mass)**	Comments
Fresh Water	Operator	Base Fluid					
			Fresh Water	7732-18-5	100.00000	90.13721	Density = 8.330
SAND - PREMIUM WHITE	Halliburton	Proppant					
			Crystalline silica, quartz	14808-60-7	100.00000	9.06064	
HYDROCHLORIC ACID 10-30%	Halliburton	Solvent					
			Hydrochloric acid	7647-01-0	30.00000	0.14832	
LoSurf-300D	Halliburton	Non-ionic Surfactant					
			Ethanol	64-17-5	60.00000	0.04964	
			Heavy aromatic petroleum naphtha	64742-94-5	30.00000	0.02482	
			Naphthalene	91-20-3	5.00000	0.00414	
			Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched	127087-87-0	5.00000	0.00414	
			1,2,4 Trimethylbenzene	95-63-6	1.00000	0.00083	
WVG-36 GELLING AGENT	Halliburton	Gelling Agent					
			Guar gum	9000-30-0	100.00000	0.04329	
BC-140	Halliburton	Crosslinker					
			Monoethanolamine borate	26038-87-9	60.00000	0.02330	

			Ethylene glycol	107-21-1	30.00000	0.01165	
Cla-Web™	Halliburton	Additive					
			Ammonium salt	Confidential	60.00000	0.02988	
MC MX 2-2822	Multi-Chem	Scale Inhibitor					
			Phosphonate of a Diamine, Sodium Salt	Proprietary	30.00000	0.00820	
			Methyl alcohol	67-56-1	30.00000	0.00820	Density = 8.765
FR-66	Halliburton	Friction Reducer					
			Hydrotreated light petroleum distillate	64742-47-8	30.00000	0.00809	
FE-1A ACIDIZING COMPOSITION	Halliburton	Additive					
			Acetic anhydride	108-24-7	100.00000	0.00495	
			Acetic acid	64-19-7	60.00000	0.00297	
MC B-8614	Multi-Chem	Biocide					
			Glutaraldehyde	111-30-8	30.00000	0.00549	
			Alkyl (C12-16) dimethylbenzylammonium chloride	68424-85-1	5.00000	0.00091	
OPTIFLO-HTE	Halliburton	Breaker					
			Walnut hulls	NA	100.00000	0.00248	
			Crystalline silica, quartz	14808-60-7	30.00000	0.00074	
SP BREAKER	Halliburton	Breaker					
			Sodium persulfate	7775-27-1	100.00000	0.00125	
HAI-404M™	Halliburton	Corrosion Inhibitor					
			Aldehyde	Confidential	30.00000	0.00027	
			Isopropanol	67-63-0	30.00000	0.00027	
			Methanol	67-56-1	30.00000	0.00027	
			1-(Benzyl)quinolinium chloride	15619-48-4	10.00000	0.00009	
			Quaternary ammonium salt	Confidential	10.00000	0.00009	
Ingredients shown above are subject to 29 CFR 1910.1200(i) and appear on Material Safety Data Sheets (MSDS). Ingredients shown below are Non-MSDS.							
		Other Ingredient(s)					
			Water	7732-18-5		0.57904	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.02482	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.00827	
		Other Ingredient(s)					
			Polyacrylamide copolymer	Confidential		0.00809	
		Other Ingredient(s)					
			Sodium chloride	7647-14-5		0.00384	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00249	
		Other Ingredient(s)					
			Bentonite, benzyl(hydrogenated tallow alkyl) dimethylammonium stearate complex	121888-68-4		0.00216	

	Other Ingredient(s)					
		Alcohols, C12-16, ethoxylated	68551-12-2		0.00144	
	Other Ingredient(s)					
		Ammonium chloride	12125-02-9		0.00135	
	Other Ingredient(s)					
		Fatty acid tall oil amide	Confidential		0.00135	
	Other Ingredient(s)					
		Cured acrylic resin	Confidential		0.00074	
	Other Ingredient(s)					
		Quaternary amine	Confidential		0.00050	
	Other Ingredient(s)					
		Silica gel	112926-00-8		0.00043	
	Other Ingredient(s)					
		Surfactant mixture	Confidential		0.00043	
	Other Ingredient(s)					
		Surfactant mixture	Confidential		0.00043	
	Other Ingredient(s)					
		Naphthenic acid ethoxylate	68410-62-8		0.00027	
	Other Ingredient(s)					
		Sorbitan monooleate polyoxyethylene derivative	9005-65-6		0.00027	
	Other Ingredient(s)					
		Sorbitan, mono-9- octadecenoate, (Z)	1338-43-8		0.00027	
	Other Ingredient(s)					
		Enzyme	Confidential		0.00012	
	Other Ingredient(s)					
		Fatty acids, tall oil	Confidential		0.00009	
	Other Ingredient(s)					
		Polyethoxylated fatty amine salt	61791-26-2		0.00009	
	Other Ingredient(s)					
		Amine salts	Confidential		0.00005	
	Other Ingredient(s)					
		Amine salts	Confidential		0.00005	
	Other Ingredient(s)					
		Quaternary amine	Confidential		0.00005	
	Other Ingredient(s)					
		Ethoxylated amine	Confidential		0.00005	
	Other Ingredient(s)					
		Crystalline Silica, Quartz	14808-60-7		0.00004	
	Other Ingredient(s)					
		Methanol	67-56-1		0.00003	
	Other Ingredient(s)					
		C.I. Pigment Red 5	6410-41-9		0.00002	
	Other Ingredient(s)					
		Cured acrylic resin	Confidential		0.00002	

		Other Ingredient(s)					
			Sodium iodide	7681-82-5		0.00001	
		Other Ingredient(s)					
			Ammonium phosphate	7722-76-1		0.00001	
		Other Ingredient(s)					
			Phosphoric Acid	7664-38-2		0.00000	
		Other Ingredient(s)					
			Sodium sulfate	7757-82-6		0.00000	

* Total Water Volume sources may include fresh water, produced water, and/or recycled water

** Information is based on the maximum potential for concentration and thus the total may be over 100%

Note: For Field Development Products (products that begin with FDP), MSDS level only information has been provided.

Ingredient information for chemicals subject to 29 CFR 1910.1200(i) and Appendix D are obtained from suppliers Material Safety Data Sheets (MSDS)

Company Ultra Petroleum
 Formation Zone #1
 Perfs 6241 - 6377
 Three Rivers 16-36T-820
 Zone #1
 Fluid System: 16-36T-820 (13) Hybrid

API 43-047-53472
 Temperature 164 °F

Liquid Additives

Stage	Fluid	Prop Conc	Prop	Slurry Vol	Slurry Rate	Treating Pressure	Pump Time	Stage	Exposure Time	WG-36 Gel	LoSurf-300D Surfactant	CLA-Web Clay Control	B-8614 Biocide	MX-2-2822 Scale Inh.	BC-140 Crosslinker	Opdlo-HTE Breaker	SP Breaker	FR-66 Fric. Red.
1	Load & Break	(ppg)	(lbs)	(bbls)	(bpm)	(psi)	(h:min:sec)		(h:min:sec)	(ppt)	(gpt)	(gpt)	(gpt)	(gpt)	(gpt)	(ppt)	(ppt)	(gpt)
2	15% HCl Acid	1000		23.8	10.0	2196	0:02:23		1:11:24		1.00	0.50	0.20					0.50
3	Pad	42258		1172.8	59.1	2897	0:19:51		1:09:01		1.00	0.50	0.20	0.55				0.50
4	0.35#/gal 20/40 White	69436	0.35	1679.4	60.8	2869	0:27:37		0:49:11		1.00	0.50	0.20	0.55				0.50
5	0.35#/gal 20/40 White	3900	0.52	2010	60.7	3358	0:01:34		0:21:34		1.00	0.50	0.20	2.00				0.50
6	0.35#/gal 20/40 White	5991	0.23	1380	60.5	3457	0:02:23		0:20:00	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
8	2.0 #/gal 20/40 White	15178	1.99	30280	60.5	3156	0:06:31		0:17:37	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
9	4.0 #/gal 20/40 White	8672	3.98	34530	60.4	3015	0:04:02		0:11:06	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
10	6.0 #/gal 20/40 White	7405	4.68	34650	60.3	3005	0:03:33		0:07:04	18.00	1.00	0.50	0.20		1.80	1.00	0.50	
11	Flush (top perf-3 bbls)	6256		149.0	42.3	3460	0:03:31		0:03:31		1.00	0.50	0.20				0.50	
13	Growler Tub Variance									50.00	1.00	0.50	2.00					0.50

15% HCl Acid:	1,000	gal
Slickwater:	130,627	gal
18# DeltaFrac 140 (13):	37,246	gal
Total Fluid:	168,873	gal
Total Slurry:	172,847	gal
20/40 White:	127,100	lbs
Total Proppant:	127,100	lbs

127,100 4115.4

Used
 % diff
 Prime
 Total

48.1

5%

1%

-6%

-10%

706	170	84	33	79	63	38	19	59
-----	-----	----	----	----	----	----	----	----

TOP PERF	6,241
BOTTOM PERF	6,377
MID PERF	6,309
BHT	164

BHT GRAD [°F/100-ft (+60°)]

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
6241	6242	3	3
6251	6252	3	3
6269	6270	3	3
6275	6276	3	3
6285	6286	3	3
6298	6299	3	3
6310	6311	3	3
6315	6316	3	3
6349	6350	3	3
6361	6362	3	3
6369	6371	3	6
6376	6377	3	3

Start Time:	8:34 AM
End Time:	9:47 AM
Customer:	Jeff Scott

43-047-53472
 S-16 / T-8S / R-20E
 Three Rivers 16-36T-820
 Ultra Petroleum
 18# DeltaFrac 140 (13) Hybrid
 July 10, 2014
 8.33
 Uintah, UT

API #
 AFE#
 Sec. / Twp. / Rng.
 Well Name
 Company
 Formation
 Fluid Systems
 Date
 Base Fluid, lb/gal
 Sales Order #
 County and State

Zone #1

Company Ultra Petroleum
 Formation Three Rivers 16-36T-820
 Zone #2 Zone #2
 Fluid System: 16-36T-820 API 43-047-53472
 6080 - 6221 Temperature 161 °F
 Fluid System: 16-36T-820 API 43-047-53472

Stage	Fluid	Prop Conc	Prop Vol	Slurry Rate	Slurry Vol	Treating Pressure	Pump Time	Stage	Exposure	WG-36	LeSurf-300D	CLA-Web	B-8514	MX 2-2822	BC-140	Optiflo-HTE	SP Breaker	FR-86
		(ppg)	(bbls)	(bpm)	(bbls)	(psi)	(h:min:sec)		(h:min:sec)	(ppt)	Surfactant	Clay Control	Blood	Scale Inh.	Crosslinker	Breaker	Breaker	Fric. Red.
1	Load & Break	170	4.0	6.9	4.0	1267	0:00:35	1:24:39	1:24:39	1.00	1.00	0.50	0.20					0.30
2	15% HCl Acid	1000	23.8	10.0	23.8	1349	0:02:23	1:24:04	1:24:04									
3	Pad	59512	1417.0	60.0	1417.0	2389	0:23:37	1:21:41	1:21:41	1.00	1.00	0.50	0.20	0.45				0.30
4	0.35#/gal 20/40 White	86442	2090.7	61.2	2090.7	2365	0:34:10	0:58:04	0:58:04	1.00	1.00	0.50	0.20	0.45				0.30
5	0.35#/gal 20/40 White	3000	1770	61.2	1770	2365	0:01:12	0:23:54	0:23:54	1.00	1.00	0.50	0.20	2.00				0.30
6	0.35#/gal 20/40 White	7029	1750	60.7	1750	2388	0:02:47	0:22:42	0:22:42	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
8	2.0 #/gal 20/40 White	18453	36790	60.7	479.0	2354	0:07:53	0:19:55	0:19:55	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
9	4.0 #/gal 20/40 White	10488	41900	60.6	294.9	2650	0:04:52	0:12:02	0:12:02	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
10	6.0 #/gal 20/40 White	8692	42600	60.6	252.8	2382	0:04:10	0:07:10	0:07:10	18.00	1.00	0.50	0.20		1.80	1.00	0.50	
11	Flush (top perf-3 bbls)	6092		48.5	145.0	2612	0:02:59	0:02:59	0:02:59	50.00	1.00	0.50	0.20					0.30
13	Growler Tub Variance																	

bbls	155,000	4945.8
23.80952		
3695.619		
1063.381		
4782.81		
4945.752		
15% HCl Acid:	gal	
Slickwater:	gal	
18# DeltaFrac 140 (13):	gal	
Total Fluid:	gal	
Total Slurry:	gal	
20/40 White:	lbs	
Total Proppant:	lbs	

TOP PERF	6,080
BOTTOM PERF	6,221
MID PERF	6,153
BHT	6,153

BHT GRAD [°F/100-ft (+60°)]

43-047-53472
 S:16 / T:8S / R:20E
 Three Rivers 16-36T-820
 Ultra Petroleum
 18# DeltaFrac 140 (13) Hybrid
 July 10, 2014
 8.33
 Uintah, UT

API #
 AFE#
 Sec. / Twp. / Rng.
 Well Name
 Company
 Formation
 Fluid Systems
 Date
 Base Fluid, lb/gal
 Sales Order #
 County and State

Zone #2

Used
 % diff
 Prime
 Total

847	202	100	39	79	76	45	23	42
-----	-----	-----	----	----	----	----	----	----

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
6080	6081	3	3
6097	6098	3	3
6119	6120	3	3
6133	6134	3	3
6144	6145	3	3
6164	6165	3	3
6174	6175	3	3
6185	6186	3	3
6193	6194	3	3
6201	6202	3	3
6209	6210	3	3
6219	6221	3	6

Start Time:	2:35 PM
End Time:	4:02 PM
Customer:	Jeff Scott

Company Ultra Petroleum
Formation Three Rivers 16-36T-820
Perts Zone #3 Temperature 158
Fluid System: 16-36T-820 (13) Hybrid

5868 - 6060
API 43-047-53472
F

Liquid Additives

Stage	Fluid	Fluid	Prop Conc	Prop	Slurry Vol	Slurry Rate	Treating Pressure	Pump Time (h:min:sec)	Stage	Exposure Time (h:min:sec)	WG-36 Gel (ppt)	LoSurf-3000 Surfactant (ppt)	CLA-Web Clay Control (ppt)	B-8614 Biocide (ppt)	MX-2-2822 Scale Inh. (ppt)	BC-140 Crosslinker (ppt)	Optifo-HTE Breaker (ppt)	SP Breaker Breaker (ppt)	FR-66 Fried. Red (ppt)
1	Load & Break	282			6.7	5.4	1260	0:01:15		1:47:40		1.00	0.50	0.20					0.50
2	15% HCl Acid	1000			23.8	10.2	1456	0:02:20		1:46:25									
3	Pad	72947			1736.8	52.8	2072	0:32:55		1:44:05		1.00	0.50	0.20	0.33				0.50
4	0.35#/gal 20/40 White	108316	0.35	39082	2620.0	60.5	2151	0:43:17		1:11:10		1.00	0.50	0.20	0.33				0.50
5	0.35#/gal 20/40 White	5004	0.37	1850	121.1	60.4	2362	0:02:00		0:27:53		1.00	0.50	0.20	2.00				0.50
6	0.35#/gal 20/40 White	5119	0.38	1830	123.9	60.4	2363	0:02:03		0:25:53	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
7	Pad	243	0.41	100	5.9	60.3	2355	0:00:06		0:23:50	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
8	2.0 #/gal 20/40 White	22793	1.97	44970	591.1	61.7	2418	0:09:35		0:23:44	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
9	4.0 #/gal 20/40 White	13301	3.87	51520	372.2	61.6	2334	0:06:02		0:14:09	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	
10	6.0 #/gal 20/40 White	10331	4.98	51500	301.5	60.0	2169	0:05:02		0:08:07	18.00	1.00	0.50	0.20		1.80	1.00	0.50	
11	Flush (top perf+3 bbls)	5928			141.1	45.8	2484	0:03:05		0:03:05		1.00	0.50	0.20					0.50
13	Growler Tub Variance										50.00	1.00	0.50	2.00					

bbls	23.80952	194,280	6037.5	Used	932.2	244.3	122.1	48.9	80.0	93.2	51.8	25.9	96.2
4582.795				% diff	1011	249	124	48	79	91	54	27	85
1233.033				Prime	8%	2%	2%			-2%	4%	4%	-12%
5839.638				Total	1011	249	124	48	79	111	54	27	85
6037.452													

15% HCl Acid:	1,000	gal
Slickwater:	192,477	gal
18# DeltaFrac 140 (13):	51,787	gal
Total Fluid:	245,265	gal
Total Slurry:	253,573	gal
20/40 White:	194,280	lbs
Total Proppant:	194,280	lbs

TOP PERF	5,868
BOTTOM PERF	6,060
MID PERF	
BHT	

BHT GRAD [F/100-ft (+60°)]

43-047-53472

API #

AFE#

Sec. / Twp. / Rng.

Well Name

Company

Formation

Fluid Systems

Date

Base Fluid, lb/gal

Sales Order #

County and State

S:16 / T:8S / R:20E

Three Rivers 16-36T-820

Ultra Petroleum

18# DeltaFrac 140 (13) Hybrid

July 10, 2014

8.33

901497055

Utah, UT

Zone #3

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
5868	5869	3	3
5880	5881	3	3
5891	5892	3	3
5903	5904	3	3
5924	5925	3	3
5934	5935	3	3
5952	5953	3	3
5984	5985	3	3
6009	6010	3	3
6020	6021	3	3
6045	6046	3	3
6058	6060	3	6

Start Time:	
End Time:	
Customer:	Joe Duncan

Simulation Design Worksheet

Company Ultra Petroleum
 Formation Three Rivers 16-36T-820
 Zone #4
 Fluid System: 16-36T-820 (13) Hybrid
 5603 - 5807

API 43-047-53472
 Temperature 154
 F

Liquid Additives

Stage	Fluid	Fluid	Prop Conc	Prop	Slurry Vol	Slurry Rate	Treating Pressure	Pump Time (h:min:sec)	Stage Time (h:min:sec)	Exposure Time	WG-36 Gel	LoSurf-300D Surfactant	CLA-Web Clay Control	B-8614 Biocide	MX-2-2822 Scale Inh.	BC-140 Crosslinker	OptiFlo-HTE Breaker	SP Breaker	FR-66 Frict. Red.
1	Load & Break	485	(ppg)	(lbs)	(bbls)	(bpm)	(psi)	(h:min:sec)	(h:min:sec)	(h:min:sec)	(ppt)	(gpt)	(gpt)	(gpt)	(gpt)	(gpt)	(ppt)	(ppt)	(gpt)
2	15% HCl Acid	1000			23.8	10.1	2470	0:02:22	1:30:50			1.00	0.50	0.20					0.50
3	Pad	56970			1356.4	54.7	2692	0:24:48	1:28:28			1.00	0.50	0.20	0.41				0.50
4	0.5#/gal 20/40 White	91782	0.46	42646	2231.2	60.3	2765	0:37:02	1:03:39			1.00	0.50	0.20	0.41				0.50
5	0.5#/gal 20/40 White	5153	0.48	2460	125.3	60.2	3001	0:02:05	0:26:37			1.00	0.50	0.20	2.00				0.50
6	0.5#/gal 20/40 White	5037	0.49	2490	122.6	60.1	3114	0:02:02	0:24:32			1.00	0.50	0.20	0.25	1.80	1.00	0.50	
7	Pad	90	0.44	40	2.2	60.1	3166	0:00:02	0:22:30			1.00	0.50	0.20	0.25	1.60	1.00	0.50	
8	2.0 #/gal 20/40 White	20073	2.01	40290	521.3	60.1	3098	0:08:41	0:22:28			1.00	0.50	0.20	0.25	1.60	1.00	0.50	
9	4.0 #/gal 20/40 White	11399	3.87	44100	318.9	60.1	2780	0:05:18	0:13:47			1.00	0.50	0.20	0.25	1.60	1.00	0.50	
10	6.0 #/gal 20/40 White	8916	4.99	44500	260.2	59.6	2529	0:04:22	0:08:29			1.00	0.50	0.20		1.60	1.00	0.50	
11	Flush (top perf+3 bbls)	5588			133.3	32.4	2368	0:04:07	0:04:07			1.00	0.50	0.20					0.50
13	Growler Tub Variance										50.00	1.00	0.50	2.00					

bbls	23,809.52	180,960	5095.4
3809.245	159,988		
1083.696	45,515		
4916.751	206,504		
5095.377	214,006		
	180,960		
	180,960		

Used 738.3 205.5 102.8 41.1 80.0 79 72 49 25 80.0

% diff 9%

Prime

% diff 2%

Prime

Total

807 210 104 40 79 72 49 25 70

TOP PERF	5,603
BOTTOM PERF	5,807
MID PERF	5,700
BHT	5,640

BHT GRAD [FF/100-R (+60°)]

43-047-53472

S:16 / T:8S / R:20E

Three Rivers 16-36T-820

Ultra Petroleum

16# DeltaFrac 140 (13) Hybrid

July 10, 2014

8.33

901497055

Uintah, UT

API #

AFE#

Sec. / Twp. / Rng.

Well Name

Company

Formation

Fluid Systems

Date

Base Fluid, lb/gal

Sales Order #

County and State

Zone #4

Start Time:	
End Time:	
Customer:	Joe Duncan

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
5603	5604	3	3
5621	5622	3	3
5641	5642	3	3
5679	5680	3	3
5690	5691	3	3
5709	5710	3	3
5721	5722	3	3
5735	5736	3	3
5747	5748	3	3
5759	5760	3	3
5793	5794	3	3
5805	5807	3	6

Company Ultra Petroleum
Formation Three Rivers 16-36T-820
Perfs 5332 - 5561
Zone #5
Fluid System: 16-36T-820 (13) Hybrid
Temperature 150
API 43-047-53472
F

Liquid Additives

Stage	Fluid	Fluid	Prop Conc	Prop	Slurry Vol	Slurry Rate	Slurry	Treating Pressure	Stage Pump Time	Exposure Time	WG-36 Gal	LoSurf-300D Surfactant	CLA-Web Clay Control	B-8614 Biocide	MX 2-2822 Scale Inh.	BC-140 Crosslinker	Optilco-HTE Breaker	SP Breaker	FR-66 Frict. Red.
1	Load & Break	228			5.4	5.2	1938	0.01:03	1:34:18	1:34:18		1.00	0.50	0.20					0.40
2	15% HCl Acid	1000			23.8	10.0	2234	0.02:23	0:26:13	1:30:53		1.00	0.50	0.20	0.38				0.40
3	Pad	61151			1456.0	58.5	2363	0.24:53	0:24:14	1:06:00		1.00	0.50	0.20	0.38				0.40
4	0.5#/gal 20/40 White	98481	0.50	49830	2422.3	60.9	2327	0:39:46	0:26:13	1:06:00		1.00	0.50	0.20	0.38				0.40
5	0.5#/gal 20/40 White	4981	0.50	2510	121.3	60.9	2423	0:02:00	0:24:14	1:06:00		1.00	0.50	0.20	2.00				0.40
6	0.5#/gal 20/40 White	5022	0.50	2520	122.3	60.8	2433	0:02:01	0:24:14	1:06:00	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
8	2.0 #/gal 20/40 White	21506	2.00	42960	558.3	60.7	2441	0:09:12	0:22:13	1:06:00	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
9	4.0 #/gal 20/40 White	12210	3.99	48660	343.2	60.6	2349	0:05:40	0:13:01	1:06:00	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
10	6.0 #/gal 20/40 White	10523	4.63	48700	303.0	60.5	2203	0:05:01	0:07:21	1:06:00	16.00	1.00	0.50	0.20		1.60	1.00	0.50	
11	Flush (top perf+3 bbls)	5311			126.5	53.9	2343	0:02:21	0:02:21		50.00	1.00	0.50	0.20					0.40
13	Growler Tub Variance																		

bbls																				
23.80952	15% HCl Acid:	1,000	gal																	
4075.048	Slickwater:	171,152	gal																	
1172.881	16# DeltaFrac 140 (11):	49,261	gal																	
5271.738	Total Fluid:	221,413	gal																	
5476.609	Total Slurry:	230,018	gal																	
	20/40 White:	195,200	lbs																	
	Total Proppant:	195,200	lbs																	

Used 788.2
% diff 830
Prime 223
Total 111

Used 788.2
% diff 830
Prime 223
Total 111

Used 788.2
% diff 830
Prime 223
Total 111

Used 788.2
% diff 830
Prime 223
Total 111

TOP PERF	5,332
BOTTOM PERF	5,561
MID PERF	5,447
BHT	5,447

BHT GRAD (°F/100-ft (+60°))

43-047-53472

S-16 / T-8S / R-20E

Three Rivers 16-36T-820

Ultra Petroleum

16# DeltaFrac 140 (13) Hybrid

July 10, 2014

8:33

Utah, UT

Zone #5

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
5332	5333	3	3
5341	5342	3	3
5366	5367	3	3
5381	5382	3	3
5390	5391	3	3
5405	5406	3	3
5419	5420	3	3
5433	5434	3	3
5449	5450	3	3
5512	5513	3	3
5529	5530	3	3
5559	5561	3	6

Start Time:	5:40 AM
End Time:	7:15 AM
Customer:	Jeff Scott

Company Ultra Petroleum
Formation Three Rivers 16-36T-820
Perfs Zone #6 Fluid System: 16Frac 140 (13) Hybrid
4800 - 5108
Temperature 142 °F
API 43-047-53472

Liquid Additives

Stage	Fluid	Prop Conc	Prop	Slurry Vol	Slurry Rate	Treating Pressure	Pump Time	Exposure Time	WG-36 Gel	LoSurf-300D Surfactant	CLAWeb Clay Control	B-8514 Biocide	Scale Inh.	BC-140 Crosslinker	Optiflo-HTE Breaker	SP Breaker	FR-66 Fric Red
		(ppg)	(lbs)	(bbls)	(bpm)	(psi)	(h:min:sec)	(h:min:sec)	(ppt)	(gpt)	(gpt)	(gpt)	(gpt)	(gpt)	(ppt)	(ppt)	(gpt)
1	Load & Break	172		4.1	7.0	2050	0:00:35	1:12:13		1.00	0.50	0.20					0.30
2	15% HCl Acid	1000		23.8	9.9	2005	0:02:24	1:11:38									
3	Pad	42528		1012.6	58.9	2640	0:17:11	1:09:14		1.00	0.50	0.20	0.53				0.30
4	0.5#/gal 20/40 White	75060	0.50	1827.6	60.7	2350	0:30:07	0:52:02		1.00	0.50	0.20	0.53				0.30
5	0.5#/gal 20/40 White	5020	0.50	122.2	60.7	2313	0:02:01	0:21:56		1.00	0.50	0.20	2.00				0.30
6	0.5#/gal 20/40 White	5036	0.51	122.7	60.7	2316	0:02:01	0:19:55	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
8	2.0 #/gal 20/40 White	16713	1.99	33260	60.5	2334	0:07:10	0:17:53	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
9	4.0 #/gal 20/40 White	9492	4.00	37950	60.4	2197	0:04:25	0:10:43	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
10	6.0 #/gal 20/40 White	7869	4.84	38100	60.4	2035	0:03:47	0:06:18	16.00	1.00	0.50	0.20		1.60	1.00	0.50	
11	Flush (top perf+3 bbls)	4680		111.0	44.0	1851	0:02:31	0:02:31	50.00	1.00	0.50	0.20					0.30
13	Growler Tub Variance																

bbls		151,900	4148.8
23.80952	15% HCl Acid:	1,000	gal
3034.286	Slickwater:	127,440	gal
931.1905	16# DeltaFrac 140 (11):	39,110	gal
3989.286	Total Fluid:	167,550	gal
4148.841	Total Slurry:	174,251	gal
	20/40 White:	151,900	lbs
	Total Proppant:	151,900	lbs

Used
% diff
Prime
Total

Average Rate 48.3

TOP PERF	4,800
BOTTOM PERF	5,108
MID PERF	4,954
BHT	4,954

BHT GRAD [°F/100-ft (+60°)]

43-047-53472

S:16 / T:8S / R:20E

Three Rivers 16-36T-820

Ultra Petroleum

16# DeltaFrac 140 (13) Hybrid

July 10, 2014

8.33

Uintah, UT

Zone #6

API #

AFE#

Sec. / Twp. / Rng.

Well Name

Company

Formation

Fluid Systems

Date

Base Fluid, lb/gal

Sales Order #

County and State

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
4800	4801	3	3
4822	4823	3	3
4845	4846	3	3
4879	4880	3	3
4888	4889	3	3
4921	4922	3	3
4934	4935	3	3
4994	4995	3	3
5040	5041	3	3
5048	5049	3	3
5053	5054	3	3
5106	5108	3	6

Start Time:	9:16 AM
End Time:	10:28 AM
Customer:	Jeff Scott

Simulation Design Worksheet

Company Ultra Petroleum
Formation Three Rivers 16-36T-820
Perfs Zone #7
4596 - 4764
Temperature 137
Fluid System: 16-36T-820 API 43-047-53472
Zone #7
Fluid System: 16-36T-820 API 43-047-53472
Zone #7

Liquid Additives

Stage	Fluid	Prop Conc	Slurry Vol	Slurry Rate	Treating Pressure	Stage Pump Time	Exposure Time	WG-36 Gel	LoSurf-300D Surfactant	CLAWeb Clay Control	B-8614 Biocide	MX-2-2822 Scale Inh.	BC-140 Crosslinker	Optiflo-HTE Breaker	SP Breaker	FR-66 Frict Red
1	Load & Break	227	5.4	7.6	1226	0:00:43	1:11:36		1.00	0.50	0.20					0.30
2	15% HCl Acid	1000	23.8	10.0	1268	0:02:23	1:10:53									
3	Pad	52324	1245.8	59.5	1902	0:20:56	1:08:30		1.00	0.50	0.20	0.52				0.30
4	0.5#/gal 20/40 White	69745	1698.1	61.0	1835	0:27:50	0:47:34		1.00	0.50	0.20	0.52				0.30
5	0.5#/gal 20/40 White	4987	121.4	61.0	1826	0:01:59	0:19:44		1.00	0.50	0.20	2.00				0.30
6	0.5#/gal 20/40 White	4978	121.1	61.0	1826	0:01:59	0:17:44	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
8	2.0 #/gal 20/40 White	15562	403.9	60.7	1854	0:06:39	0:15:45	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
9	4.0 #/gal 20/40 White	6685	197.6	60.7	1798	0:03:15	0:09:06	16.00	1.00	0.50	0.20	0.25	1.60	1.00	0.50	
10	6.0 #/gal 20/40 White	7873	223.0	60.4	1696	0:03:42	0:05:51	16.00	1.00	0.50	0.20		1.60	1.00	0.50	
11	Flush (top perf+3 bbls)	4525	107.7	50.1	1753	0:02:09	0:02:09		1.00	0.50	0.20					0.30
13	Growler Tub Variance							50.00	1.00	0.50	2.00					

bbls	143,700	4142.4
23.80952		
3138.286	1,000 gal	
830.9048	131,808 gal	
3993	34,898 gal	
4142.411	167,706 gal	
	173,981 gal	
	143,700 lbs	
	143,700 lbs	

Used
% diff
Prime
Total

49.2

558.4	166.7	83.4	33.3	80.0	55.8	34.9	17.4	35.5
626	165	82	32	79	56	38	19	34
626	165	82	32	79	56	38	19	34

TOP PERF	4,596
BOTTOM PERF	4,764
MID PERF	4,680
BHT	4,680


BHT GRAD [°F/100-ft (+60°)]

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
4596	4597	3	3
4604	4605	3	3
4611	4612	3	3
4622	4623	3	3
4631	4632	3	3
4677	4678	3	3
4683	4684	3	3
4716	4717	3	3
4725	4726	3	3
4734	4735	3	3
4741	4742	3	3
4762	4764	3	6

Start Time:	12:21 PM
End Time:	1:31 PM
Customer:	Jeff Scott

43-047-53472
S.16 / T.8S / R.20E
Three Rivers 16-36T-820
Ultra Petroleum
18# DeltaFrac 140 (13) Hybrid
July 10, 2014
8:33
Utah, UT
Zone #7


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 116 Inverness Drive East, Suite #400, Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 16-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0699 FSL 1311 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047542890000
PHONE NUMBER: 303 645-9809 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/1/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input checked="" type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This well has converted to be an injection well through UIC Permit No. UT22312-10686 as of 05/01/2015. Please see the attached paker and casing test data, which was passed on 05/05/2015.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 10, 2015		
NAME (PLEASE PRINT) Jasmine Allison	PHONE NUMBER 307 367-5041	TITLE Sr. Permitting Analyst
SIGNATURE N/A	DATE 6/9/2015	



Data Collection Report

Gauge Information	
Serial Number	467805
Model	5KPSIXP2I
Message Store	-----
Units	PSI

Run Info	
Start Time	1/6/70 4:45:21 PM
Stop Time	1/6/70 5:27:29 PM
Logging Interval	5



Certificate of Calibration

Report number FASTCAL-C00036

Manufacturer	Model	Gauge Number	Serial Number	Calibration Date	Expiration Date
Barton	202A-MFG-3470	MFG-3470-3K	MFG-3470	1/26/2015	7/25/2015

Model Uncertainty
+/- ASME 3A of span (0.25%)

All instrument calibrations are verified for accuracy before they are shipped. The recommended calibration interval for this instrument is 6 months from the date of verification. Your particular quality assurance requirements may supersede this recommendation.

As Received Condition: In tolerance

As Left Condition: In tolerance

Laboratory ambient conditions throughout this calibration were:

Temperature 70 to 72° F
 Humidity 30 to 32% RH
 Pressure 82 to 84 kPa

Reference Standards used in this calibration are traceable to the National Institute of Standards and Technology of the United States, through the following report numbers:

Manufacturer	Model	Serial Number	Report Number	Due Date	Reference Uncertainty
Crystal Engineering	15KPSIBXP2I	465591	194285	5-Apr-15	0-20% of FS: $\pm(0.02\%$ of FS); 20%-100% of FS: $\pm(0.1\%$ of Rdg)

This certificate shall not be reproduced except in full, without written approval.


 Justin Anthony

Laboratory Representative

Temp Test	As Left
Test Points	
38	38
74	75
109	108

Quality Representative

Test Results

Report number FASTCAL-C00036

As Received Test Results

3000 PSI

Reference Reading	Gauge Reading	Allowable Tolerance	Difference	Difference (% of FS)	Condition
0	0	7	0	0.00%	Pass
1500	1500	7	0	0.00%	Pass
2999	3000	7	1	0.03%	Pass
2400	2405	7	5	0.17%	Pass
600	600	7	0	0.00%	Pass
0	0	7	0	0.00%	Pass

As Left Test Results

3000 PSI

Reference Reading	Gauge Reading	Allowable Tolerance	Difference	Difference (% of FS)	Condition
0	0	7	0	0.00%	Pass
1500	1500	7	0	0.00%	Pass
2999	3000	7	1	0.03%	Pass
2400	2405	7	5	0.17%	Pass
600	600	7	0	0.00%	Pass
0	0	7	0	0.00%	Pass

AR Head correction: 0 PSI
 AL Head correction: 0 PSI

Certificate of Calibration

Report number FASTCAL-C00035

Manufacturer	Model	Gauge Number	Serial Number	Calibration Date	Expiration Date
Crystal	5KPSIXP2I	467805 5K	467805	1/26/2015	7/26/2015

Model Uncertainty
+/- ASME 4A of span (0.1%)

All instrument calibrations are verified for accuracy before they are shipped. The recommended calibration interval for this instrument is 6 months from the date of verification. Your particular quality assurance requirements may supersede this recommendation.

As Received Condition: In tolerance

As Left Condition: In tolerance

Laboratory ambient conditions throughout this calibration were:

Temperature 70 to 72° F
Humidity 30 to 32% RH
Pressure 82 to 84 kPa

Reference Standards used in this calibration are traceable to the National Institute of Standards and Technology of the United States, through the following report numbers:

Manufacturer	Model	Serial Number	Report Number	Due Date	Reference Uncertainty
Crystal Engineering	15KPSIBXP2I	465591	194285	5-Apr-15	0-20% of FS: $\pm(0.02\%$ of FS); 20%-100% of FS: $\pm(0.1\%$ of Rdg)

This certificate shall not be reproduced except in full, without written approval.

Justin Anthony
Justin Anthony

Laboratory Representative

Quality Representative

Test Results

Report number FASTCAL-C00035

As Received Test Results

5000 PSI

Reference Reading	Gauge Reading	Allowable Tolerance	Difference	Difference (% of FS)	Condition
0	0	5	0	0.00%	Pass
1000	999	5	-1	-0.02%	Pass
2000	1998	5	-2	-0.04%	Pass
3000	2997	5	-3	-0.06%	Pass
4000	4000	5	0	0.00%	Pass
5000	5000	5	0	0.00%	Pass
4000	4000	5	0	0.00%	Pass
3000	3000	5	0	0.00%	Pass
2000	2000	5	0	0.00%	Pass
1000	1000	5	0	0.00%	Pass
0	0	5	0	0.00%	Pass

As Left Test Results

5000 PSI

Reference Reading	Gauge Reading	Allowable Tolerance	Difference	Difference (% of FS)	Condition
0	0	5	0	0.00%	Pass
1000	999	5	-1	-0.02%	Pass
2000	1998	5	-2	-0.04%	Pass
3000	2997	5	-3	-0.06%	Pass
4000	4000	5	0	0.00%	Pass
5000	5000	5	0	0.00%	Pass
4000	4000	5	0	0.00%	Pass
3000	3000	5	0	0.00%	Pass
2000	2000	5	0	0.00%	Pass
1000	1000	5	0	0.00%	Pass
0	0	5	0	0.00%	Pass

AR Head correction: 0 PSI
 AL Head correction: 0 PSI

Mercer Valve Co., Inc.

Repair Division

Vernal, Utah

Ph: 435-789-4780

866-612-1853

Fax: 435-789-4787

VALVE TEST REPORT

CUSTOMER NAME:	<u>CROSSFIRE</u>	DATE:	<u>02/12/15</u>
LOCATION:	<u>N/A</u>	PO #	<u>N/A</u>
EQUIPMENT:	<u>N/A</u>	PSV:	<u>N/A</u>

ORIGINAL NAMEPLATE INFORMATION

MANUFACTURER	<u>MERCER</u>	MODEL	<u>91-17D61T14E1</u>
SERIAL NUMBER	<u>1014209</u>	SIZE	<u>1X1</u>
SET PRESSURE	<u>1510</u> PSI	CAPACITY	<u>3065</u> SCFM
ORIFICE	<u>D</u>		

TEST DATA

TEST MEDIA	<u>AIR</u>	CAPACITY	<u>4312</u> SCFM
SET PRESSURE	<u>2130</u> PSI	ACTUAL SET PRESSURE	<u>2130</u> PSI
LEAKAGE AT RESET	<u>NONE</u>	EXTERNAL LEAKAGE	<u>NONE</u>
REPAIR SERIAL NO.	<u>UR-10922F</u>	MAWP	<u>N/A</u>
PRETEST 1ST POP	<u>LEAK</u> PSI	MODEL	<u>91-17D61T14E1</u>
SECOND TEST	<u>LEAK</u> PSI		
QUALITY CONTROL INSP	<u>SHAWN POULEN</u>		

COMMENTS: COMPLETE BREAKDOWN OF PSV. CLEAN AND INSPECTED ALL PARTS

INSTALL 05-015 SPRING REASSEMBLE PSV AND SET TO 2130 PSI AND REPAIR KIT INSTALLED

Bar Seal	Re-Installed	N/A (No Valve)
Inlet	X	X
Outlet	X	X

Mercer Valve Co., Inc.

Repair Division

Vernal, Utah

Ph: 435-789-4780

866-612-1853

Fax: 435-789-4787

VALVE TEST REPORT

CUSTOMER NAME:	<u>CROSSFIRE</u>	DATE:	<u>02/12/15</u>
LOCATION:	<u>N/A</u>	PO #	<u>N/A</u>
EQUIPMENT:	<u>N/A</u>	PSV:	<u>N/A</u>

ORIGINAL NAMEPLATE INFORMATION

MANUFACTURER	<u>MERCER</u>	MODEL	<u>91-17D61T14E1</u>
SERIAL NUMBER	<u>1014207</u>	SIZE	<u>1X1</u>
SET PRESSURE	<u>1510</u> PSI	CAPACITY	<u>3065</u> SCFM
ORIFICE	<u>D</u>		

TEST DATA

TEST MEDIA	<u>AIR</u>	CAPACITY	<u>4312</u> SCFM
SET PRESSURE	<u>2130</u> PSI	ACTUAL SET PRESSURE	<u>2130</u> PSI
LEAKAGE AT RESET	<u>NONE</u>	EXTERNAL LEAKAGE	<u>NONE</u>
REPAIR SERIAL NO.	<u>UR-10924F</u>	MAWP	<u>N/A</u>
PRETEST 1ST POP	<u>LEAK</u> PSI	MODEL	<u>91-17D61T14E1</u>
SECOND TEST	<u>LEAK</u> PSI		
QUALITY CONTROL INSP	<u>SHAWN POULEN</u>		


COMMENTS: COMPLETE BREAKDOWN OF PSV. CLEAN AND INSPECTED ALL PARTS

INSTALL 05-015 SPRING REASSEMBLE PSV AND SET TO 2130 PSI AND REPAIR KIT INSTALLED

Car Seal	Re-Installed	N/A (No Valve)
Inlet	X	X
Outlet	X	X

Crossfire, LLC - Job Hazard Analysis

Equipment/ Job Location:
Ultra Resources
16-36T-820 Three Rivers
South Ouzar, UT
 Date: 5-5-13
 Start Time (AM/PM) 8:30 End Time (AM/PM) 5:00



Job Description:
Pressure Test Casing
1172 PSI / 1171 PSI
112 PM / 1145
 Name of Person Completing Form: Ron Lago
 JHA Translated by Bi-Lingual Individual for Spanish Speaking on Site ☒ Yes ☐ No

Permit(s) Required: ☐ Hot Work ☐ Ground Disturbance ☐ Confined Space ☐ Energy Isolation (LOTO) ☐ Lifting Operation ☐ Other ☒ No Permit Required
 SIMOPs or Multi-Crew Activity ☐ Yes ☒ No Name of Person in Charge Ron Lago Person Works for (Company Name) Crossfire

Activity / Sequence of Job Tasks <small>List the tasks required to perform the activity in the sequence they are carried out.</small>	Energy Sources <small>(circle all that apply)</small>	Specific Hazard Identified <small>Against each task list the hazards that could cause injury when the task is performed. Can the hazard hurt me or anyone working on the site?</small>	Environmental Impacts <small>Could there be a release to the air, soil or water? Will a waste be generated?</small>	Actions and Risk Control Measures <small>List the actions and control measures required to eliminate or minimize the risk of injury arising from the identified hazard and impact in the environment.</small>	Responsible Person <small>Write the name of the person responsible for implementing the control measure identified</small>
<u>Install Pressure test Tree</u>	<u>Motion; Chemical; Radiation; Electrical; Gravity; Heat/Cold; Biological; Pressure</u>	<u>Exposure Isolation Heavy lifting</u>	<u>None</u>	<u>Ensure proper Isolation before working on High pressure tree lift with your knees not year back</u>	<u>RL</u>
<u>Pressure test</u>	<u>Motion; Chemical; Radiation; Electrical; Gravity; Heat/Cold; Biological; Pressure</u>	<u>High Pressure</u>	<u>None</u>	<u>Stay at least 75' Away from line with high pressure</u>	<u>RC</u>
<u>Remove Pressure Test tree</u>	<u>Motion; Chemical; Radiation; Electrical; Gravity; Heat/Cold; Biological; Pressure</u>	<u>Isolation Heavy lifting</u>	<u>None</u>	<u>Ensure proper Isolation Do not work on line if high pressure is present lift with your knees not year back</u>	<u>RC</u>
<input checked="" type="checkbox"/> <u>Hands</u>	<u>Motion; Chemical; Radiation; Electrical; Gravity; Heat/Cold; Biological; Pressure</u>	<u>Pinch points Sharp or abrasive objects</u>	<u>None</u>	<u>Wear Hand protection at all times Ensure proper hand placement</u>	<u>RC</u>

Was Emergency Response Plan and Actions Reviewed and Agreed? ☒ Yes ☐ No If No, give reason _____

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Ultra Petroleum Inc. Operator Account Number: N 4045
Address: 116 Inverness Drive East Suite 400
city Denver
state CO zip 80112 Phone Number: (307) 367-5041

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
	Multiple Wells						Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
D	See List	19892				8/10/15	
Comments: Assign multiple wells to a new common entity number. List of wells attached. <u>TR16 CTB North</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
D	See List	19893				8/10/15	
Comments: <u>TR16 CTB South</u>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Jasmine Allison

Name (Please Print)



Signature

Sr. Permitting Analyst

8/6/2015

Title

Date

WellCode	WellName	API	Current Entity Number	QtrQtr	Section	Township	Range	County	SpudDate
TR16 CTB North									
TR16-11-820	THREE RIVERS 16-11-820	4304753474	19262	SWNW	16 8S	20E	UINTAH	28-Dec-13	
TR16-11T-820	THREE RIVERS 16-11T-820	4304754352	19557	NWNW	16 8S	20E	UINTAH	29-Jun-14	
TR16-12-820	THREE RIVERS 16-12-820	4304753475	19263	SWNW	16 8S	20E	UINTAH	06-Jan-14	
TR16-12T-820	THREE RIVERS 16-12T-820	4304754353	19558	NWNW	16 8S	20E	UINTAH	23-Jun-14	
TR16-21-820	THREE RIVERS 16-21-820	4304753229	19024	NENW	16 8S	20E	UINTAH	25-May-13	
TR16-21T-820	THREE RIVERS 16-21T-820	4304754364	19578	SENW	16 8S	20E	UINTAH	30-Jul-14	
TR16-22A-820	THREE RIVERS 16-22A-820	4304754365	19579	SENW	16 8S	20E	UINTAH	26-Jul-14	
TR16-31-820	THREE RIVERS 16-31-820	4304753495	19269	NWNE	16 8S	20E	UINTAH	13-Jan-14	
TR16-41-820	THREE RIVERS 16-41-820	4304752110	18356	NENE	16 8S	20E	UINTAH	31-Jan-12	
TR16-42L-820	THREE RIVERS 16-42L-820	4304754269	19491	SENE	16 8S	20E	UINTAH	20-Jul-14	
TR16-42T-820	THREE RIVERS 16-42T-820	4304754292	19471	NENE	16 8S	20E	UINTAH	06-May-14	
TR16-44T-820	THREE RIVERS 16-44T-820	4304754356	19561	SENE	16 8S	20E	UINTAH	15-Jul-14	
TR16 CTB South									
TR16-13T-820	THREE RIVERS 16-13T-820	4304754339	19492	NWSW	16 8S	20E	UINTAH	02-Jun-14	
TR16-14T-820	THREE RIVERS 16-14T-820	4304754340	19493	NWSW	16 8S	20E	UINTAH	06-Jun-14	
TR16-22-820	THREE RIVERS 16-22-820	4304753230	18961	NENW	16 8S	20E	UINTAH	31-May-13	
TR16-23-820	THREE RIVERS 16-23-820	4304753231	19037	SESW	16 8S	20E	UINTAH	15-Jun-13	
TR16-24-820	THREE RIVERS 16-24-820	4304753232	19038	SESW	16 8S	20E	UINTAH	08-Jun-13	
TR16-26T-820	THREE RIVERS 16-26T-820	4304754351	19556	NESW	16 8S	20E	UINTAH	16-Jul-14	
TR16-32-820	THREE RIVERS 16-32-820	4304753494	19185	SWNE	16 8S	20E	UINTAH	27-Sep-13	
TR16-32T-820	THREE RIVERS 16-32T-820	4304754290	19470	NWNE	16 8S	20E	UINTAH	01-May-14	
TR16-33-820	THREE RIVERS 16-33-820	4304753496	19161	SWNE	16 8S	20E	UINTAH	12-Nov-13	
TR16-33T-820	THREE RIVERS 16-33T-820	4304754354	19559	NWSE	16 8S	20E	UINTAH	04-Jul-14	
TR16-34-820	THREE RIVERS 16-34-820	4304753472	19278	SWSE	16 8S	20E	UINTAH	24-Jun-14	
TR16-34T-820	THREE RIVERS 16-34T-820	4304754355	19560	NWSE	16 8S	20E	UINTAH	11-Jul-14	
TR16-36T-820	THREE RIVERS 16-36T-820	4304754289	19529	SESE	16 8S	20E	UINTAH	16-Jun-14	
TR16-43-820	THREE RIVERS 16-43-820	4304752057	18683	NESE	16 8S	20E	UINTAH	09-Aug-12	
TR16-44-820	THREE RIVERS 16-44-820	4304753473	19268	SESE	16 8S	20E	UINTAH	19-Jun-14	
TR16-46T-820	THREE RIVERS 16-46T-820	4304754348	19530	SESE	16 8S	20E	UINTAH	11-Jun-14	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: ULTRA RESOURCES INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 116 Inverness Drive East, Suite #400 , Englewood, CO, 80112		8. WELL NAME and NUMBER: Three Rivers 16-36T-820
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0699 FSL 1311 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 16 Township: 08.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047542890000
PHONE NUMBER: 303 645-9809 Ext		9. FIELD and POOL or WILDCAT: THREE RIVERS
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/26/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <input type="text" value="First Injection"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This well was previously approved to be converted to an injection well. First injection commenced 5/26/2015. Please see the attached daily summary of work performed.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 10, 2015		
NAME (PLEASE PRINT) Jasmine Allison	PHONE NUMBER 307 367-5041	TITLE Sr. Permitting Analyst
SIGNATURE N/A	DATE 9/4/2015	

ULTRA RESOURCES, INC.
DAILY COMPLETION REPORT FOR 04/29/2015 TO 05/01/2015

Well Name	THREE RIVERS 16-36T-820	Fracs Planned	7
Location:	UINTAH County, UTAH(SESE 16 8S 20E)	AFE#	140618, 141077, 150067
Total Depth Date:	06/18/2014 TD 6,499	Formation:	(Missing)
Production Casing:	Size 5 1/2 Wt 17 Grade J-55 Set At 6,487	GL:	KB: 4,698

Date:	04/29/2015		
Tubing:	OD: 2.875" ID: 2.307" Joints: 141" Depth Set: 4,589"	PBTD:	6,486
Supervisor:	JIM BURNS		
Work Objective:	Mi/RU workover rig		
Contractors:	DOUBLE HOOK 1, WILLIES, KNIGHT, JCS, RHETTS, USANCO		
Completion Rig:	Double Hook 1	Supervisor Phone:	43592992974
Upcoming Activity:	Well sent to sales		
Activities			
0600-0700	CREW TRAVEL, SAFETY MEETING		
0700-1730	R/d Unit, road rig from Three Rivers 16-34T-820 to loc. Spot in r/u unit, r/u willies hot oil, heated csg w/60-bbls prod. Wtr @ 200 degr., unseated pump, flushed tbg w/ 40-bbls prod. Wtr @ 200 degr. Pooh l/d w/ 1 1/2" x 30' polish rod, 1-2' 2-4' 1-6' x 7/8" pony rods, 41-7/8" 4per mms rods, 36- 7/8" 4per mms rods, 145- 3/4" 4per mms rods, 30- 1" 4per mms rods, pump. Changed over to tbg equip. blow dwn csg. HSM on handling tbg proper lifting, buddy system, stay hydrated, slow down. N/d well head, unlanded tbg, Tac was sheared, n/u bope, l/d hanger, p/u 1- jnt 2 7/8" tbg, tag fill 12' from landing depth. l/d 1- jnt, Pooh s/b w/ 143- jnts 2 7/8" tbg, sheared 1/4 turn TAC, 60- jnts 2 7/8" tbg, Psu, 1-jnt 2 7/8" tbg, 4' x 2 7/8" pup jnt, desander, 4' x 2 7/8" pup jnt, perge valve. Found : Thick wax on BHA. P/u Tally & rih w/ 4 3/4" rock bit, 5 1/2" csg scrapper, x-over, 42- jnts 2 7/8" tbg. EOT @ 1,342'. SIT, Flow Csg to sales		
1730-1830	CREW TRAVEL		
0000-0000	Preparing for casing test and slow leak. Packed off packer several times again and still bled off ~350psi over weekend. Reset the packer and got a good test. EPA test completed.		
Costs (\$):	Daily: 5,704	Cum: 26,173	AFE: 95,250

Date:	04/30/2015		
Tubing:	OD: 2.875" ID: 2.307" Joints: 141" Depth Set: 4,589"	PBTD:	6,486
Supervisor:	JIM BURNS		
Work Objective:	Blow well down		
Contractors:	DOUBLE HOOK 1, WEATHERFORD, JCS, WILLIES, KNIGHT, USANCO		
Completion Rig:	Double Hook 1	Supervisor Phone:	43592992974
Upcoming Activity:	Well sent to sales		
Activities			
0600-0700	CREW TRAVEL, SAFETY MEETING		
0700-1700	Blow down well, Rih w/ 206 total jnts 2 7/8" tbg, tagged fill @ 6,432', btm perf. @ 6,377', 55' rat hole. Pooh l/d w/ 160- jnts 2 7/8" tbg, r/u willies hot oil, flushed & rinsed off oily tbg on l.d & o.d w/ 60-bbls prod. Wtr @ 200 degr., r/d willies, continue pooh l/d w/ 206- total jnts 2 7/8" prod. Tbg, x-over, 5 1/2" csg scrapper, 4 3/4" rock bit. Spotted in 2 7/8" Nickel coated tbg. P/u tally & rih w/ re-entry guide, 1.875 XN profile, 6' x 2 7/8" nickel coated pup jnt, 5 1/2" AS1-X nickel coated PKR, 84- Jnts 2 7/8" nickel coated tbg, EOT @ 2,798', SIT Flow csg to sale		
1700-1800	CREW TRAVEL		
Costs (\$):	Daily: 12,547	Cum: 38,720	AFE: 95,250

Date:	05/01/2015		
Tubing:	OD: 2.875" ID: 2.307" Joints: 141" Depth Set: 4,589"	PBTD:	6,486
Supervisor:	JIM BURNS		
Work Objective:	Blow well down		
Contractors:	DOUBLE HOOK 1, WILLIES, KNIGHT, WEATHERFORD, RHETTS, NALCO		
Completion Rig:	Double Hook 1	Supervisor Phone:	43592992974
Upcoming Activity:	RDMO		
Costs (\$):	Daily: 1,410	Cum: 40,130	AFE: 95,250

Sundry Number: 65958 API Well Number: 43047542890000



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 8

1595 Wynkoop Street
Denver, CO 80202-1129
Phone 800-227-8917
www.epa.gov/region08

NOV 05 2015

Ref: 8P-W-UIC

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Kelly Bott
Regulatory and Environmental Manager
Ultra Resources, Inc.
116 Inverness Drive East, Suite 400
Englewood, Colorado 80112

43 047 54289
Three Rivers 16-36T-820
16 85 20E

RE: Underground Injection Control
One-year Limited Authorization to Inject Extension
Five Ultra Petroleum Class II EOR Wells
Permit information shown below
Uintah County, Utah

Dear Ms. Bott:

The U.S. Environmental Protection Agency Region 8 has reviewed your well information submittal of October 23, 2015, and followed-up with Ultra Petroleum during a meeting on October 29. The EPA concurs with the latest Ultra data regarding the time and pressure build-up relationship in the Green River Formation, Three Rivers Field. Regarding preparations for conducting permit-required Radioactive Tracer Surveys (RATS) and Step Rate Tests (SRT) for the five wells, Ultra will need at least several months of additional injecting beyond the current Limited Authorization to Inject (LATI) before the target Maximum Allowable Injection Pressure (MAIP) is attained. The EPA has determined that a one-year LATI is necessary. The current LATI expires November 21, 2015.

The EPA requires monthly status reports (due by the 10th of the following month) on the injection progress for each well (e.g., progress of pressure buildup, volume of water injected, etc.). It is expected that once any well under the LATI reaches the MAIP, Ultra will conduct the RATS, SRT and any other tests required under the permits and promptly submit the data to the EPA. The EPA will evaluate the results of the testing and approve an authorization to inject as appropriate on a well by well basis.

The following five wells are approved for this LATI for a one-year period beginning November 21, 2015, and expiring on November 21, 2016.

<u>Permit Number</u>	<u>Well Number</u>	<u>API Number</u>	<u>MAIP</u>
UT22308-10679	TR16-22-820	43-047-53230	1345 psig
UT22309-10680	TR16-24T-820	43-047-54341	1100 psig
UT22310-10682	TR16-32T-820	43-047-54290	1330 psig
UT22311-10685	TR16-34T-820	43-047-54355	1265 psig
UT22312-10686	TR16-36T-820	43-047-54289	1280 psig

Ultra is authorized to commence injection into these five wells at the respective MAIP listed above for a period of one-year. Ultra must receive prior authorization from the Director in order to inject at pressures greater than the permitted MAIP during any test. Please remember that it is your responsibility to be aware of, and to comply with, all conditions of these permits. If you have any questions regarding this approval, please call Bill Gallant at (303) 312- 6455 or (800) 227-8917, extension 312-6455, or Bruce Suchomel at (303) 312-6001 or (800) 227-8917, extension 312-6001.

Sincerely,



Darcy O'Connor
Acting Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

cc:

Uintah & Ouray Business Committee

Honorable Shaun Chapoose, Chairman
Edred Secakuku, Vice-Chairman
Reannin Tapoof, Executive Assistant

Bartholomew Stevens, Superintendent
BIA - Uintah & Ouray Indian Agency

Bart Powaukee
Environmental Director
Ute Indian Tribe

Minnie Grant
Air Quality Coordinator
Ute Indian Tribe

Bruce Pargeets
Assistant Director of Energy & Minerals Dept.
Ute Indian Tribe.

Brad Hill
Utah Division of Oil, Gas, and Mining

Robin Hansen
Fluid Minerals Engineering Office
BLM - Vernal Office



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 8

1595 Wynkoop Street
Denver, CO 80202-1129
Phone 800-227-8917
www.epa.gov/region8

NOV 16 2016

Ref: 8WP-SUI

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Kelly Bott
Regulatory and Environmental Manager
Ultra Resources, Inc.
116 Inverness Drive East
Suite 400
Englewood, Colorado 80112

Re: Underground Injection Control
180-Day Limited Authorization to Inject Extension
Three Ultra Petroleum Class II EOR Wells
Uintah County, Utah

16 85 20E

Dear Ms. Bott:

The Ultra Resources, Inc. (Ultra) letter with attached information was received by the U.S. Environmental Protection Agency Region 8 on October 21, 2015. The submittal partially completed the "Prior to Commencing Injection" requirements for Final Class II UIC series of Final Permits listed below. The ongoing Monthly LATI Reports, Step Rate Tests, Radioactive Tracer Test, chemical tracer testing and workover reports were reviewed by the EPA in October 2016 to support this extension.

Approved LATI's


<u>Permit Number</u>	<u>Well Number</u>	<u>API Number</u>	<u>MAIP</u>
UT22310-10682	TR16-32T-820	43-047-54290	1020 psig
UT22311-10685	TR16-34T-820	43-047-54355	1125 psig
UT22312-10686	TR16-36T-820	43-047-54289	1115 psig

As of the date of this letter, Ultra is authorized to extend injection into these three wells at the respective Maximum Allowable Injection Pressure (MAIP) listed above for a period of 180 days. The permits require a Step Rate Test, well workover reports and other data prior to receiving authorization to inject beyond the time necessary to start continuing injection activities.

Ultra must receive prior authorization from the Director in order to inject at pressures greater than the permitted MAIP during any test. Please remember that it is Ultra's responsibility to be aware of, and to comply with, all conditions of these three enhanced recovery injection well permits.

If you have questions regarding the above action, please call William Gallant at (303) 312-6455 or (800) 277-8917, extension 312-6455. Results of testing and any other activities concerning these wells should be mailed directly to the attention of William Gallant, at the letterhead address citing Mail Code: 8WP-SUI.

Sincerely,

A handwritten signature in black ink, appearing to read 'Darcy O'Connor', with a long horizontal line extending to the right.

Darcy O'Connor
Assistant Regional Administrator
Office of Water Protection

cc:

Uintah & Ouray Business Committee
Chairman Shaun Chapoose
Vice-Chairman Edred Secakuku
Reannin Tapoof, Executive Assistant

Bartholomew Stevens, Superintendent
BIA - Uintah & Ouray Indian Agency

Antonio Pingree, Deputy Superintendent
BIA - Uintah & Ouray Indian Agency

Kirby Arrive, Natural Resources Director
Ute Indian Tribe

Bruce Pargeets, Energy & Minerals Director
Ute Indian Tribe Energy & Minerals Dept.

Brad Hill, Oil and Gas Permitting Manager
Utah Division of Oil, Gas, and Mining

Jerry Kenczka, Assistant Field Manager for Lands and Minerals
BLM - Vernal Office